

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-23441-00-00
Spot: SENWSW Sec/Twnshp/Rge: 17-14S-19W
1650 feet from S Section Line, 4290 feet from E Section Line
Lease Name: MEIER Well #: 7
County: ELLIS Total Vertical Depth: 3819 feet

Operator License No.: 5252
Op Name: NIXON, R P OPERATIONS, INC
Address: 207 W 12TH
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3819	0	w/125 sxs cmt
SURF	8.625	200	0	w/155 sxs cmt

\$124.12

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/20/2006 12:00 PM
Plug Co. License No.: 5252 Plug Co. Name: NIXON, R P OPERATIONS, INC
Proposal Rcvd. from: DUANE ACHTERBERG Company: NIXON, R P OPERATIONS, INC Phone: (785) 628-3834

Proposed Plugging Method: Ordered 250 sxs cement and 500# hulls.
Perforated 4 1/2" at 2100' - 1500' - 750'.

Plugging Proposal Received By: ROGER MOSES WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 10/20/2006 1:00 PM KCC Agent: ROGER MOSES

Actual Plugging Report:

Squeezed 215 sxs cement and 500# hulls down 4 1/2" casing.
Max. P.S.I. 600#. S.I.P. 500#.
8 5/8" x 4 1/2" annulus full of cement - visual.
Total 215 sxs 60/40 pozmix - 10% gel and 500# hulls.

Perfs:

Remarks: ALLIED CEMENTING COMPANY. HERTEL TANK-WATER.

Plugged through: CSG

District: 04

Signed

Roger Moses
(TECHNICIAN)

INVOICED

DATE 10/30/06

INV. NO. 2007060747

OCT 25 2006

RECEIVED

OCT 27 2006

KCC WICHITA

R.P. NIXON OPERATIONS
207 W. 12TH

#7 MEIER

17-14-19W
SE NW SW

HAYS, KS 67601

CONTR JAY-LAN CORPORATION

CTY ELLIS

GEOLOGIST DAN NIXON


FIELD ETHEL SW

2195 KB

ELV 2190 GL SPD 4/28/83 CARD ISSUED 8/4/83

IP P 40 BOPD, TR WTR

GOR SD 3797-3819 OA



API 15-051-23,441

LOG	Tops	Depth/Datum
TOP		3198-1003
HEEB		3449-1254
TOR		3473-1278
LANS		3495-1300
BKC		3740-1545
MARM		3777-1582
GOR SD		3794-1599
RTD		3819-1624

8 5/8 " 200; 4 1/2 " 3818.5

NO DST'S

MICT - CO, PF (GOR SD) 3797-3802, FU 15' OIL, AC 500G
(15%), SWB LD, TR OIL, CO TO 3819', SWB .93 BOPH / 6 HRS.
FU 600' OIL / 14 HRS, SET PKR AT 3802', AC 500G (15%), TST
(GOR SD OH), REC LD & SWB 3.5 BOPH, (TR W), FU 3100' OIL /
14 HRS, SET PKR AT 3509', PF (SC) 3/ 1478, SQZ'D W/CMT &
CIRC TO SURF, PULL PKR AT 3509', POP, P 9 BOPD / 1ST 2
DAYS, DECL & STAB AT 40 BOPD & TR WTR

COPYRIGHT 1983
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS