

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-25576-00-00

Spot: NWSWNE

Sec/Twnshp/Rge: 14-14S-20W

1550 feet from N Section Line,

2160 feet from E Section Line

Lease Name: BRENDA

Well #: 14-1

County: ELLIS

Total Vertical Depth: 3870 feet

Operator License No.: 33335

Op Name: IA OPERATING, INC.

Address: 900 N TYLER ROAD #14
WICHITA, KS 67212

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	209		

\$ 125.78

Well Type: DH

UIC Docket No:

Date/Time to Plug: 10/24/2006 1:00 AM

Plug Co. License No.: 30606

Plug Co. Name: MURFIN DRILLING CO., INC.

Proposal Rcvd. from: ANDY DINKEL

Company: MURFIN DRILLING CO., INC.

Phone: (785) 462-7541

Proposed Plugging Method: Ordered out 175 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: JAY PFEIFER

WitnessType: NONE

Date/Time Plugging Completed: 10/24/2006 2:30 AM

KCC Agent: JAY PFEIFER

Actual Plugging Report:

Perfs:

1st. Plug at 1475' w/25 sxs.
2nd. Plug at 675' w/75 sxs.
3rd. Plug at 250' w/40 sxs.
4th. Plug at 40' w/10 sxs. 8 5/8" wiper plug.
Rathole with 15 sxs.
Mousehole with 10 sxs.

INVOICED
DATE 10/30/06
2007060749

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed

Jay Pfeifer

(TECHNICIAN)

OCT 26 2006

RECEIVED
OCT 27 2006 PKI
KCC WICHITA