

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-141-20, 171-00-00

SE-NE-SW, Sec. 20, T 10 S, R 14 W/E

1650 feet from N(S) section line

2310 feet from W(E) section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5146

Lease Name ELLIOTT Well # 1

Operator Name & Address: RAINS + WILLIAMSON OIL CO. INC.

County OSBORNE

435 PAGE COURT
220 WEST DOUGLAS
WICHITA, KANS. 67202

Well Total Depth 3521 feet \$114.43

Conductor Pipe: Size 0 feet

Surface Casing: Size 8 5/8 feet 270

Abandoned Oil Well ___ Gas Well ___ Input Well ___ SWD Well ___ D&A X

Other well as hereinafter indicated

Plugging Contractor RAINS + WILLIAMSON License Number 62

Address 435 PAGE COURT - 220 W. DOUGLAS, WICHITA MS. 67202

Company to plug at: Hour: 7:00 PM Day: 5th Month: JUNE Year: 1983

VERBAL PLUGGING ORDERS GIVEN TO BOB MLOTZ

(company name) RAINS + WILLIAMSON DRILL (phone) 316-265-9686

were: 8 5/8" 270 FT SR. CML #/225 ST COMMON SUN SET (By Sun Out)

ORDER 160 ST 50/50 Foamix 4% GEL-3% CA-CL AND 8 5/8" PLUG

SPOT WITH DRILL STEM - WITH HEAVY MUD BETWEEN ALL PLUGS.

NO ARBUCKLE, ELEV. 1839 - ANV. 1039.

Signed [Signature] (TECHNICIAN) (2010)

Plugging Operations attended by Agent?: All ___ Part ___ None X

Operations Completed: Hour: 7:00 PM Day: 5th Month: JUNE Year: 1983

ACTUAL PLUGGING REPORT

ORDERED 160 ST 50/50 Foamix 4% GEL-3% CA-CL AND 8 5/8" PLUG

SPOTTED WITH DRILL STEM - WITH HEAVY MUD BETWEEN ALL PLUGS.

1st Plug @ 1050 FT #/20 ST CNT, 2nd Plug @ 570 FT #/80 ST CNT

3rd Plug @ 275 FT #/40 ST CNT, 4th Plug HALL'S PLUG @ 40 FT #/10 CNT

10 ST IN RAT HOLE (CIRCULATE) (CEMENTED BY SUN CNT.)

Remarks:

I hereby certify that the above plugging instructions were given as herein stated and that I (did / did not) observe this plugging.

Signed [Signature] (TECHNICIAN) (2010)

FORM CP-2/3 Rev. 9-82

INVOICED
DATE 6-17-83
INV. NO. 4617-6

RECEIVED
STATE CORPORATION COMMISSION
6-13-83
JUN 13 1983

CONSERVATION DIVISION
Wichita, Kansas