

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 141-20198-00-00

C N/2 N/2 N/2, Sec. 15, T 10 S, R 14 W/E

330 feet from N/E section line

2640 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6725

Lease Name Meyers Well # 2

Operator: Eric Waddell

County Osborne

Name & Address Box 349  
Natoma Ks.

Well Total Depth 3799 feet 123.47

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 217

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well B&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor R.E.C. Dring License Number 9087

Address Box 296 Hays Ks.

Company to plug at: Hour: 9:30 AM Day: 6 Month: 3 Year: 19 84

VERBAL PLUGGING ORDERS GIVEN TO John Weis

(company name) R.E.C. Dring (phone) \_\_\_\_\_

were: order 185 sk. cem. 50/50 portmix 600 gal 30% c.c.

1.5x hulls 1.8 5/8 plug 1.5x Flow Seal

Heavy mud between all plugs

Pump com. down drill pipe

Elev. 2043 Anhydrite 1183-1215 Arbuckle No.

Dakota 1500

Signed Dale F. Batthazor  
(TECHNICIAN)

543-840

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None (circled)

Operations Completed: Hour: 3:15 PM Day: 6 Month: 3 Year: 19 84

ACTUAL PLUGGING REPORT circulated @ 1190 for 20 mi.

25 sk @ 1190

100 sk @ 840 mixed with 1.5x flow seal.

40 sk @ 270 - 1.5x hulls pushed plug to 40'

10 sk @ 40

10 sk Rat hole

Remarks: \_\_\_\_\_

Cementing co. Allied.

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 12 1984  
3-12-84  
CONSERVATION DIVISION  
Wichita, Kansas

I hereby certify that the above plugging instructions were given as herein stated and that I (did / did not) (circled) observe this plugging.

Signed Dale F. Batthazor  
(TECHNICIAN)

FORM CP-2/3  
Rev. 9-82

INVOICED

DATE 3-14-84

0755