

4-071089

2-25

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15-181-20,295-00-00

C NW NW /4 SEC. 32, 09 S, 42 W  
660 feet from N section line  
660 feet from W section line

Operator license # 30442

Lease JN Cloyd-Jones well # 11-32

Operator: JN Exploration & Production  
Limited Partnership

County Sherman

Address: P.O. Box 7167  
Billings, Montana 59103-7167  
Kent J. Stolz

Well total depth 5495 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 377 feet

178.58

Aband. oil well \_\_\_\_, Gas well \_\_\_\_, Input well \_\_\_\_, SWD \_\_\_\_, D & A X

Plugging contractor: Murfin Drilling License# -

Address: Wichita, Kansas 67202

Company to plug at: Hour: P.M. Day: 25 Month: February Year: 94

Plugging proposal received from: Keith Vanpelt

Company: Murfin Drilling Phone: 406-248-2222

Were: 8 5/8" - 377' S.P. cwc. w/250 sxs. 60/40 pozmix - 2% gel -  
3% Cal.Cl. by Allied. Elv. 3976' - Anhy. 3332'. Marrow sand well.  
No circulation problems. Mud condition 49 vis. - 9.0 weight - 8.2 water  
loss - 350 pmm cl. at 5373'. Proposal 190 sxs. 60/40 pozmix - 6% gel -  
1 sx. flocele. Circulate hole - 42 - 45 vis. mud. Spot and displace all  
cement through drill pipe - heavy mud between all plugs. 1st. plug 25 sxs  
cmt. @ 3340' - 2nd. plug 100 sxs. cmt. w/1sx. F.C. @ 2620' - 3rd. plug @ 420' w/  
40 sxs. cmt. 5th. plug 10 sxs. cmt @ 40'. 15 sxs in rathole-circulate.  
Plugging Proposal Received by: Marion J. Schmidt  
Plugging operations attended by agent? All [ ], Part [ ], None [ X ]

Completed: Hour: 12:15 P.M., Day: 25, Month: February, Year: 94

Actual plugging report: Murfin ordered 190 sxs. 60/40 pozmix - 6% gel -  
1/4# flocele. Spotted and displace all cement through drill pipe with  
heavy mud between all plugs.  
1st. plug at 3340' w/25 sxs. cement.  
2nd. plug at 2620' w/100 sxs. cement w/1 sx. flocele.  
3rd. plug at 420' w/40 sxs. cement.  
4th. plug at 40' w/10 sxs. cement.  
15 sxs. in rathole (circulate)

Remarks: Allied Cement Company  
Condition of casing (in hole): GOOD X BAD Anhy. plug: YES X NO  
Bottom plug (in place): YES, CALC, NO X Dakota plug: YES X, NO  
Plugged through TUBING X, CASING. Elevation: 3976 GL

RECEIVED  
STATE CORPORATION COMMISSION  
03-09-1994  
MAR 09 1994  
CONSERVATION DIVISION  
Wichita, Kansas

I did [ ] did not [ X ] observe the plugging.

*Marion J. Schmidt*  
(agent)

INVOICED  
DATE 3-11-94  
INV. NO. 40089