

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-065-01437-00-00  
Spot: NWNESE Sec/Twnshp/Rge: 18-9S-21W  
2310 feet from S Section Line, 990 feet from E Section Line  
Lease Name: SUTOR B Well #: 4  
County: GRAHAM Total Vertical Depth: 3792 feet

Operator License No.: 5363  
Op Name: BEREXCO, INC.  
Address: PO BOX 20380  
WICHITA, KS 67208

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		3760		
PROD	5.5	3784	0	w/unknown sxs cmt
SURF	8.625	161	0	w/unknown sxs cmt

\$ 123.24

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/31/2006 10:00 AM  
Plug Co. License No.: 5363 Plug Co. Name: BEREXCO, INC.  
Proposal Rcvd. from: DENNIS KIRMER Company: BEREXCO, INC. Phone: (785) 628-6101

Proposed Plugging Method: Ordered out 325 sxs 60/40 pozmix - 10% gel - 500# hulls.  
CIBP at 3760'.  
Well squeezed at 1442' - 1475' w/75 sxs; 2600' - 2920' w/250 sxs; 3120' - 3153' w/100 sxs.

Plugging Proposal Received By: JAY PFEIFER Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 10/31/2006 4:00 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Perforated casing at 1830' - 1000' - 150'.  
Swaged onto 5 1/2" - mixed and pumped 200 sxs with 500# hulls.  
Opened annulus and circulated cement up 8 5/8".  
Shut in and continued with 100 sxs cement.  
Max. P.S.I. 500#. S.I.P. 50#.

Perfs:

Top	Bot	Thru	Comments
3642	3645		
3526	3530		
3486	3491		
3120	3153		100 SXS
2600	2920		250 SXS
1442	1475		CSG LEAK-75 SX

**INVOICED**  
DATE 11-8-06  
INV. NO. 2007060761

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

*ND*

Signed

*Jay Pfeifer*

(TECHNICIAN)

*[Signature]*

NOV 02 2006

RECEIVED  
NOV 06 2006  
KCC WICHITA

PEEL-HARDMAN & APPLEMAN #4 SUTOR B 18-9-21W 22  
 NW NE SE

Contr. PEEL DRILLING CO. GRAHAM County

E 2285 Comm. Comp. 7-7-50 IP 3000 BOPD  
 PHY POT

Tops	Depth	Datum
ARB	3783	-1498
T.D.	3792	-1507

Casing  
 8" 161 SWB 20 BOPH/5 HRS.  
 5" 3784 ACID 500  
 SWB 46 BOPH

MOREL POOL

+	+	+
+	+	+
+	+	+

INDEPENDENT OIL & GAS SERVICE  
 WICHITA, KANSAS