

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-23541-00-00
Spot: W2W2SE Sec/Twnshp/Rge: 6-10S-20W
1250 feet from S Section Line, 2175 feet from E Section Line
Lease Name: TK Well #: 1
County: ROOKS Total Vertical Depth: 3880 feet

Operator License No.: 5363
Op Name: BEREXCO, INC.
Address: PO BOX 20380
WICHITA, KS 67208

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	264		

\$ 126.10

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 10/23/2006 3:00 PM
Plug Co. License No.: 31548 Plug Co. Name: DISCOVERY DRILLING
Proposal Rcvd. from: TOM ALM Company: DISCOVERY DRILLING Phone: (785) 623-2920

Proposed Plugging Method: Order 225 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: HERB DEINES WitnessType: NONE
Date/Time Plugging Completed: 10/23/2006 6:00 PM KCC Agent: HERB DEINES

Actual Plugging Report:

1st. Plug at 3780' w/25 sxs.
2nd. Plug at 1775' w/25 sxs.
3rd. Plug at 1025' w/100 sxs.
4th. Plug at 315' w/40 sxs.
5th. Plug at 40' w/10 sxs.
Rathole with 15 sxs.
Mousehole with 10 sxs.

Perfs:

INVOICED
DATE 11-8-06
INV. NO. 2007060761

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed



(TECHNICIAN)

NOV 03 2006

RECEIVED
NOV 06 2006
KCC WICHITA