

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-08163-00-00
Spot: SESWNW Sec/Twnshp/Rge: 11-14S-15W
2970 feet from S Section Line, 4290 feet from E Section Line
Lease Name: DUMLER B Well #: 3
County: RUSSELL Total Vertical Depth: 3282 feet

Operator License No.: 31070
Op Name: EAGLE RIVER ENERGY CORPORATIO
Address: 7060 S. YALE #609
TULSA, OK 74136

String	Size	Depth (ft)	Pulled (ft)	Comment
COND	12.5	530		400 SX \$106.67
PROD	5.5	3282	0	580 SX
SURF	10.75	903	0	w/unknown sxs cmt

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/31/2006 9:00 AM
Plug Co. License No.: 32332 Plug Co. Name: FISCHER PIPE TESTING, INC. DBA FISCHER WELL SERVICE
Proposal Rcvd. from: GEORGE RICE Company: EAGLE RIVER ENERGY CORPORA Phone: (620) 793-2645

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 10% gel - 600# hulls.
Plug through tubing.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/31/2006 12:45 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Perfed at 1550' - 900' - 450'.
Tied on backside - pumped 50 sxs cement - good circulation - backside full.
Tubing set at 2015' - pumped 80 sxs cement with 400# hulls.
Pulled tubing to 1000' - pumped 70 sxs cement with 200# hulls.
Pulled tubing out and squeezed with 150 sxs cement.
Max. P.S.I. 400#. S.I.P. 150#.

Perfs:

Top	Bot	Thru	Comments
3277	3281		
3066	3068		
3054	3056		

INVOICED
DATE 11-8-06
INV. NO. 2007060764

Remarks: ALLIED CEMENTING COMPANY-TICKET #33201.

Plugged through: TBG

District: 04

Signed

(TECHNICIAN)

NOV 02 2006

RECEIVED
Form CP-2/3
NOV 06 2006
KCC WICHITA

DARBY PETROLEUM CO.

3-B

DIMLER

11-14-15W
SE SW NW

Contr.

RUSSELL

County

E 1865

Comm. 4-25-37


Comp. 5-26-37

IP 1091 BOPD

Tops	Depth	Datum
ANHY	902	
LANS	3025	
ARB	3272	
CG GORH	3277	
TD	3282	

Casing
6" 3272

2 1/2" BO 3036-60



INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS