

6090154

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-141-20, 210-00-00

NW 1/4, SEC. 10, T. 10 S, R. 15 W 1/2

3630 feet from N/S section line

5040 4950 feet from N/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9745

Operator: True Extension Oil

Name & Address c/o Bruce Ward

Rt. 1

Natoma, Ka. 67651

Lease Name Cherry Well # 3-10

County Osborne

Well Total Depth 3578 feet 116.29

Conductor Pipe: Size - feet -

Surface Casing: Size 8 5/8 feet 246

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Reelin Drilling License Number 5671

Address W. Hwy. 40 Russell, Ka. 67665

Company to plug at: Hour: Day: 7 Month: August Year: 19 84

Plugging proposal received from Paula

(company name) Reelin Drilling (phone) 913-483-5355

were: Order 160 sks. 50/50 permit, 10% gel, 3% Cal. Cl. + 8 5/8" wiper plug, spot all plugs w/ drill pipe w/ heavy mud between all plugs.

Plugging Proposal Received by Edwin A. Schumacher
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 3:30 AM Day: 8 Month: August Year: 19 84

ACTUAL PLUGGING REPORT 1st 1190' w/ 80 sks.
2nd 675' w/ 1sk. Allo-Flake + 80 sks.
3rd 300' w/ 40 sks.
4th 40' solid bridge 1sk. hulls 10 sks.
10 sks. in rat hole

Remarks: Elevation - 1974', Anhydrite - 1187', Arbusch - no (Allid)

INVOICED

RECEIVED

I (did / did not) observe this plugging.

DATE 8-23-84

INV. NO. 3353

AUG 20 1984 Signed Edwin A. Schumacher
8-20-84 (TECHNICIAN)

CONSERVATION DIVISION
Wichita, Kansas

SH
Aug 17
13