

6010185

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-141-20209-00-00

NE, SEC. 9, T 10 S, R 15 W

2310 feet from N/E section line

990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9745

Lease Name Chesney Well # 5-9

Operator: Tru Ext. oil co.

County Osborne

Name & Address R.R. 1

Well Total Depth 3555 115.54 feet

Natoma Ks.

Conductor Pipe: Size _____ feet

67651

Surface Casing: Size 8 5/8 feet 238

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Revlin Drilg. Co. License Number 5671

Address Box 293 Russell Ks.

Company to plug at: Hour: 10 AM Day: 14 Month: 8 Year: 19 84

Plugging proposal received from Revlin Drilg. Co.

(company name) Revlin Drilg. (phone) _____

were: order 185 sx cement 50/50 pozmix 6% Gel. 3% C.C.

1. 5x hulls 1. 8 5/8 plug 1. 5x flow seal

Heavy mud between all plugs.

Pump cement down drill pipe.

Elev. 1924 Anhydrite 1134-68 Arbuckle No.

Dakota 1600 Plugging Proposal Received by Dale F. Balthazor (TECHNICIAN)

324-650

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 11 PM Day: 14 Month: 8 Year: 19 84

ACTUAL PLUGGING REPORT circulated @ 1150 for 15 mi.

25 sx @ 1150

100 sx @ 650 mixed with 1sx flow seal

40 sx @ 240 dumped 1sx hulls pushed plug to 40'

10 sx @ 40

10 sx in Rat Hole

Remarks: cementing co. Allied

(If additional description is necessary, use BACK of this form.)

(did) (did not) observe this plugging

DATE 8-29-84

INV. NO. 3466 8-14

RECEIVED STATE CORPORATION COMMISSION 8-27-84 AUG 27 1984

Dale F. Balthazor (TECHNICIAN) 8-24-84

CONSERVATION DIVISION Wichita, Kansas

FORM CP-2/3 Rev. 01-84