

4- 041404

9-23

212
P

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

D-20,057
API number: 15-141-20,062-00-00

90' WC NE NE /4 SEC. 09, 10 S, 15 W
660 feet from N section line
750 feet from E section line

Operator license# 6588

Lease Hogan well # 1

Operator: Woodman-Iannitti Oil Co.

County Osborne

Address: P.O. Box 308
Great Bend, Kansas 67530

Well total depth 3700 feet P.B. 1050'
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 239 feet
w/160 sx.

Aband. oil well , Gas well , Input well , SWD X, D & A

Plugging contractor: B.J. Services License# -

Address: Hays, Kansas 67601

Company to plug at: Hour: 9:00A.M. Day: 23 Month: September Year: 92

Plugging proposal received from: Dick Iannitti

Company: Woodman-Iannitti Oil Co. Phone: 316-792-2921

Were: 4 1/2" casing set @ 3668' w/150 sx. cement. Perf. @ 810'- 840'.
Anhy. Perf. @ 1215' c.w. 400 sx. Squeezed @ 615' w/200 sx. W.L.M. 915'.
Perf. @ 880' squeezed with 250 sx. Perf. @ 660' - 690' with 300 sx.
Perf. and squeezed @ 525' w/100 sx. Found hole @ 700' when drilling
out after squeeze. Drilled to 915' C.I.B.P. @ 3290'.
Ordered 100 sx. 60/40 pozmix - 6% gel. with 1/4# F.C.
Cedar Hill SWD

Plugging Proposal Received by: Dennis L. Hamel

Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 10:30P.M., Day: 23, Month: September, Year: 92

Actual plugging report: Casing good to 700' - tested. Hooked-up to
4 1/2" casing. Pumped in 60 sx. cement with 1/4# flocele.
Max. P.S.I. 950#. S.I.P. 900#.

Remarks:

Condition of casing(in hole): GOOD X BAD Anhy. plug: YES X NO
Bottom plug(in place): YES X, CALC X, NO Dakota plug: YES X, NO
Plugged through TUBING , CASING X. Elevation: GL

I did[X] / did not[] observe the plugging.

INVOICED

DATE 10-12-92

INV. NO. 36416

RECEIVED
STATE CORPORATION COMMISS
10-5-92
OCT 5 1992
CONSERVATION DIVISION
Wichita, Kansas

(agent)

Form CP-2/3