

6070014

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-141-20,167-00-00
SE-NW-NW, Sec. 10, T 10 S, R 15 W/E

990 feet from N/S section line

990 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6588

Lease Name HOGAN Well # 6

Operator: WOODMAN + IANNITTI OIL
Name & Address 1008 DOUGLASS BLDG.
WICHITA, MO 67202

County OSBORNE

Well Total Depth 3600 feet \$177.00

Conductor Pipe: Size 0 feet

Surface Casing: Size 8 5/8 feet 258

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor WOODMAN + IANNITTI License Number TAG. 25 5122

Address 1008 DOUGLASS BLDG. WICHITA, MO. 67202

Company to plug at: Hour: 5:00 PM Day: 30 Month: SEPT Year: 19 83

VERBAL PLUGGING ORDERS GIVEN TO VERNON DUNLAP.

(company name) WOODMAN + IANNITTI OIL INC. (phone) 316-265-7650

were: 8 5/8" 258 FT 50 CUM 1 1/160 SK COMMON 2% GEL-3% CA-CL. (BY SUN)
ORDER 170 SK 50 1/2 Formix 4% GEL-3% CA-CL. AND 8 5/8" PLUG.

SPOT WITH DRILL STEM-TURN HOLE OVER, HEAVY MUD BETWEEN ALL PLUGS.
NO AIRBUCKLE

Signed Vernon Dunlap
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 6:15 PM Day: 30th Month: SEPT. Year: 19 83

ACTUAL PLUGGING REPORT

ORDERED 170 SK 50 1/2 Formix 4% GEL-3% CA-CL. AND 8 5/8" PLUG.

SPOTTED WITH DRILL STEM-TURNED HOLE OVER, HEAVY MUD BETWEEN PLUGS.

1st PLUG @ 1200 FT 1/20 SK CMT., 2nd PLUG @ 750 FT 1/80 SK CMT.

3rd PLUG @ 270 FT 1/50 SK CMT., 4th PLUG. HULL'S PLUG @ 40 FT 1/10 SK CMT. SOLID BRIDGE

10 SK IN RAT HOLE (CIRCULATE) (CEMENTED BY SUN CMT)

Remarks: _____

I hereby certify that the above plugging instructions were given as herein stated and that I (did / did not) observe this plugging.

RECEIVED STATE CORPORATION COMMISSION
10-11-83

DATE 10-17-83 OCT 11 1983

INV. NO. 5792

Signed Vernon Dunlap
(TECHNICIAN)