

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

**KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117**

Form CP-4
December 2003
**Type or Print on this Form
Form must be Signed
All blanks must be Filled**

Lease Operator: Arnold E. Kraft
 Address: 434 Iris Rd Sw Gridley, Ks 66852
 Phone: (620) 836-4570 Operator License #: 6227
 Type of Well: Oil DH per Shirley KCC 11-7-06 Docket #: _____
 (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
 The plugging proposal was approved on: 09/20/2006 (Date)
 by: Mike Heffron (KCC District Agent's Name)
 Is ACO-1 filed? Yes No If not, is well log attached? Yes No
 Producing Formation(s): List All (If needed attach another sheet)
Squirrel Sand Depth to Top: 1274 Bottom: 1294 T.D. _____
Mississippian Depth to Top: 1610 Bottom: 1649 T.D. _____
 _____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 031-22252-0000
 Lease Name: Wiley
 Well Number: 7
 Spot Location (QQQQ): SW - SW - NE - NE
990 Feet from North / South Section Line
930 Feet from East / West Section Line
 Sec. 14 Twp. 23 S. R. 14 East West
 County: Coffey
 Date Well Completed: 09/20/2006
 Plugging Commenced: 09/20/2006
 Plugging Completed: 09/20/2006

*KCC
PKT
11-7-06
per
C-1
sus sw ne not
good spot.*

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Kansas City	water	700	950	8"	40 ft	
Squirrel	Oil	1274	1294			
Mississippian	Oil	1610	1649			

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Well was plugged following initial drilling. Drilling mud was used with a 50 ft. cement plug pumped on bottom (1599-1649).
Drilling mud was used with another 50ft. cement plug pumped at 700 ft. (650-700). Drilling mud was used again with a cement plug pumped from 200 ft. to the surface. Consolidated Oil Well Services provided the cement.

Name of Plugging Contractor: Sky Drilling License #: 33557
 Address: 800 W, 47th St. Kansas City. MO 64112
 Name of Party Responsible for Plugging Fees: Arnold E. Kraft
 State of Kansas County, Coffey, ss.
Arnold E. Kraft

(Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) x Arnold E Kraft

(Address) 434 Iris Rd Sw Gridley, KS 66852

SUBSCRIBED and SWORN TO before me this 27 day of October, 2006
Gina M. Audiss My Commission Expires: 3-5-2010
 Notary Public

Mail to: KCC - Conservation Division, 130 S. ~~Market~~ Robinson, Wichita, Kansas 67202

RECEIVED

OCT 30 2006

KCC WICHITA





CONSOLIDATED
OIL WELL
SERVICES, INC.
AN INFINITY COMPANY

REMIT TO
Consolidated Oil Well Services, Inc.
Dept. 1228
Denver, CO 80256

MAIN OFFICE
P.O. Box 884
Chanute, KS 66720
620/431-9210 • 1-800/467-8676
FAX 620/431-0012

INVOICE

Invoice # 209247

Invoice Date: 09/25/2006 Terms:

Page 1

KRAFT, ARNOLD
434 IRIS ROAD SW
GRIDLEY KS 66852
() -

WILEY 7
14-23-14
8889
09/20/06

Part Number	Description	Qty	Unit Price	Total
1131	60/40 POZ MIX	108.00	9.3500	1009.80
1118B	PREMIUM GEL / BENTONITE	450.00	.1400	63.00
Description		Hours	Unit Price	Total
195	MIN. BULK DELIVERY	1.00	275.00	275.00
495	P & A NEW WELL	1.00	800.00	800.00
495	EQUIPMENT MILEAGE (ONE WAY)	75.00	3.15	236.25

Parts:	1072.80	Freight:	.00	Tax:	56.86	AR	2440.91
Labor:	.00	Misc:	.00	Total:	2440.91		
Sublt:	.00	Supplies:	.00	Change:	.00		

RECEIVED

OCT 30 2006

Signed _____

Date _____

KCC WICHITA

BARTLESVILLE, OK
P.O. Box 1453 74005
918/338-0808

EUREKA, KS
820 E. 7th 67045
620/583-7664

OTTAWA, KS
2631 So. Eisenhower Ave. 66067
785/242-4044

GILLETTE, WY
300 Enterprise Avenue 82716
307/686-4914

THAYER, KS
8655 Dorn Road 66776
620/839-5269

CONSOLIDATED OIL WELL SERVICES, INC.
P.O. BOX 884, CHANUTE, KS 66720
620-431-9210 OR 800-467-8676

TICKET NUMBER 08889
LOCATION Ottawa, KS.
FOREMAN Jim Green

TREATMENT REPORT & FIELD TICKET
CEMENT

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
9-20-06	4418	Wiley #7	14	23	14	CF
CUSTOMER Arnold Kraft			TRUCK #	DRIVER	TRUCK #	DRIVER
MAILING ADDRESS 434 Iris Rd SW			495	Cas Ken		
CITY Gridley			195	Bill Div		
STATE KS			481	JIMERE		
ZIP CODE 66852						

JOB TYPE Plug well HOLE SIZE 6 7/8" HOLE DEPTH 1659.9' CASING SIZE & WEIGHT -
CASING DEPTH -0- DRILL PIPE -0- TUBING -0- OTHER -
SLURRY WEIGHT 14.5" SLURRY VOL - WATER gal/sk - CEMENT LEFT in CASING -
DISPLACEMENT - DISPLACEMENT PSI - MIX PSI - RATE -

REMARKS: Establish circulation thru drill pipe. Mixed and pumped 50' plug
Displaced to TD 1659.9' (15sk) Pull drill steel to 700' mixed and pumped
15sk and displaced. Pull drill steel to 200'. Mixed and pumped 10sk
circulating cement to surface. Pull drill steel, top hole off to surface. 5sk
Mixed and pumped 10sk in Rat hole filling to surface.
Used 100 sk 6 7/8 Poz Mix 4% Gel total

ACCOUNT CODE	QUANTITY of UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
5405H	One	PUMP CHARGE Plug one well		800. ⁰⁰
5406	75	MILEAGE		236. ²⁵
5407	min.			275. ⁰⁰
1131	108 sks	6 7/8 Poz Mix		1009.80
111813	400"	Premium Gel		63. ⁰⁰
		RECEIVED		2384.05
		OCT 30 2006		
		KCC WICHITA		
		Tax 5.3%		56.86
		SALES TAX		
		ESTIMATED TOTAL		2440.91

AUTHORIZATION _____

TITLE WOT# 209247

DATE _____