

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Tengasco, Inc.
Address: PO Box 458 Hays, KS 67601
Phone: (785) 625-6374 Operator License #: 32278
Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 10-09-06 (Date)
by: Herb Deines (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Arbuckle Depth to Top: 3795 Bottom: 3799 T.D. 3799

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-163-03431-00-00
Lease Name: Croffoot A
Well Number: #7
Spot Location (QQQQ): _____ - N/2 - NE - NE
4950 Feet from North / South Section Line
660 Feet from East / West Section Line
Sec. 11 Twp. 10 S. R. 20 East West
County: Rooks
Date Well Completed: 12-27-1957
Plugging Commenced: 10-9-06
Plugging Completed: 11-2-06 10-9-06 Rce

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Arbuckle	Oil & water	235'	0	8-5/8"	11-5-1957	
		3795'	0	5-1/2'	11-16-1957	

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

10-9-06 Ran tbg to 3200'. Mixed & pumped 255 sx. Cmt circ to surface. Pulled tbg. Tied onto 5-1/2". Squeezed w/ 145 sx to 300 PSI. Total cement 400 sx 60/40 poz w/ 10% gel & 800# hulls.
11-2-06 Tied onto 8-5/8" csg. Mixed & pumped 25 sx 60/40 poz. Pres to 300 PSI

KCC 11/7/06 per per CP 2/3

Name of Plugging Contractor: Xtreme Well Service Tengasco, Inc License #: 33369 32278
Address: PO Box 337 Ellinwood, KS 67526
Name of Party Responsible for Plugging Fees: Tengasco, Inc.
State of Kansas County, Ellis, ss.
Gary Wagner

(Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Gary Wagner
(Address) PO Box 458 Hays, KS 67601

SUBSCRIBED and SWORN TO before me this 3rd day of Nov, 202006
Linda K. Pfannenstiel My Commission Expires: 2-5-08
Notary Public

RECEIVED
NOV 06 2006

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

