

API NUMBER 15-181-20-295-00-00

LEASE NAME JN CLOYD-JONES

WELL NUMBER #11-32

660 Ft. from N Section Line

660 Ft. from W Section Line

SEC. 32 TWP. 9S RGE. 42 ~~XXXX~~ (W)

COUNTY SHERMAN

Date Well Completed 2/25/94

Plugging Commenced 2/25/94

Plugging Completed 2/25/94

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR JN EXPLORATION & PRODUCTION LIMITED PARTNERSHIP

ADDRESS P. O. BOX 7167, BILLINGS, MT 59103-7167

PHONE# (406) 248-2222 OPERATORS LICENSE NO. 30442

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on FEBRUARY 24, 1994 (date)

by MERRION SMITH - HAYES KCC DISTRICT (KCC District Agent's Name).

Is ACO-1 filed? YES If not, is well log attached? _____

Producing Formation N/A Depth to Top _____ Bottom T.D. 5000'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
MARMATON	WATER	4848'	4856'	NONE		
MORROW	WATER	5338'	5354'			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set
WELL P & A'D AS PER INSTRUCTIONS FROM KCC. PLUG #1 = 25 SXS AT 3340' ACROSS ANHYDRITE; PLUG #2 = 100 SX AT 2620'
ACROSS DAKOTA: PLUG #3 = 40 SX AT 420' ACROSS SURFACE CASING SHOE; PLUG #4 = 10 SX AT 40' FOR SURFACE PLUG; PLUG #5 = 15 SX IN RATHOLE. TOTAL OF 190 SX 60:40 POZ WITH 6% GEL AND 1 SX FLOCELE.

Name of Plugging Contractor MURFIN DRILLING COMPANY License No. 30606

Address 250 N. WATER, SUITE 300, WICHITA, KANSAS 67202

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: JN EXPLORATION & PRODUCTION LIMITED PARTNERSHIP

STATE OF MONTANA COUNTY OF YELLOWSTONE, ss.

KENT J. STOLZ (Employee of Operator) ~~XXXXXXXXXXXX~~ o

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Kent J. Stolz

(Address) P. O. BOX 7167, BILLINGS, MT 59103-7167

SUBSCRIBED AND SWORN TO before me this 10TH day of MARCH, 19 94

Catherine D. [Signature]
 Notary Public
 STATE OF MONTANA

My Commission Expires: 12-14-95

USE ONLY ONE SIDE OF EACH FORM

MAR 18 1994
03-14-1994 Form CP-4
 Revised 05-88
 COMMISSIVE DIVISION
 Wichita, Kansas