

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Osborne SEC. 10 TWP. 10S RGE. 15 E/W
Location as in quarters or footage from lines:
SE NW NW

Lease Owner Woodman & Iannitti Oil Company
Lease Name Hogan Well No. 6
Office Address 1022 Union Center, Wichita, Kansas 67202
Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole
Date Well Completed September 30, 1983
Application for plugging filed September 30, 1983
Plugging commenced September 30, 1983
Plugging completed September 30, 1983
Reason for abandonment of well or producing formation _____

Locate Well
correctly on above
Section Platt.

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman
Producing formation _____ Depth to top _____ bottom _____ T.D. 3600'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set.


- 20 sx. @ 1200'
- 80 sx. @ 750'
- 50 sx. @ 270'
- 10 sx. @ 40'
- 10 sx in Rathole
- 170 sx. 50/50 Poz-mix, 4% Gel, 3% CC
- Plug down 6:15 PM, 9-30-83

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sun Oilwell Cementing

STATE OF Kansas COUNTY OF Sedgwick, ss.
K.T. Woodman (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) K.T. Woodman
1022 Union Center, Wichita, KS 67202
(Address)



SUBSCRIBED AND SWORN TO before me this 20th day of October, 19 83
Catherine J. Lewis
Notary Public.

My Commission expires: March 24, 1986



K. T. WOODMAN
 RES. PHONE 733-0418
 OFF. PHONE 265-7650
 WICHITA, KANSAS

D. J. IANNITTI
 PHONE 792-2921
 GREAT BEND, KANSAS

WOODMAN & IANNITTI DRILLING COMPANY

Rotary Drilling Contractors

1022 UNION CENTER
 150 N. MAIN
 WICHITA, KANSAS 67202

October 17, 1983

Company:	Woodman & Iannitti Oil Company
Farm:	Hogan #6
Location:	SE NW NW
Section:	10-10S-15W
County:	Osborne
Contractor:	Woodman & Iannitti Drilling Company
Total Depth:	3600'
Comm:	September 25, 1983
Comp:	September 30, 1983
Casing:	8-5/8" 24# set @ 258' w/160 sx.

Figures Indicate Bottom Formations:

10	Post Rock
258	Sand, Clay, Post Rock
940	Shale & Sand
1197	Shale, Red Bed
1233	Anhydrite
1560	Shale
2085	Shale
2318	Lime & Shale
2598	Lime & Shale
2847	Shale & Lime
3020	Lime & Shale
3147	Lime & Shale
3275	Lime & Shale
3365	Lime
3475	Lime & Shale
3562	Lime & Shale
3600	Lime

I certify the above to be a true and correct copy of the Drillers Log to the best of my knowledge and belief.

WOODMAN & IANNITTI DRILLING COMPANY

K. T. Woodman
 K.T. Woodman, Partner