

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING APPLICATION**  
Please TYPE Form and File ONE Copy

Form CP-1  
September 2003  
This Form must be Typed  
Form must be Signed  
All blanks must be Filled

API # 15 - 035-02109 -00-00 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued,

indicate original spud or completion date \_\_\_\_\_.

Well Operator: W. D. Short Oil Co., LLC KCC License #: 33608  
(Owner / Company Name) (Operator's)

Address: P.O. Box 729 City: Oxford

State: Kansas Zip Code: 67119 Contact Phone: ( 620 ) 455 - 3576

Lease: Brown Well #: 4 Sec. 2 Twp. 34 S. R. 5  East  West

C - NE - NE - SW Spot Location / QQQQ County: Cowley

2310 Feet (in exact footage) From  North /  South (from nearest outside section corner) Line of Section (Not Lease Line)

2310 Feet (in exact footage) From  East /  West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One:  Oil Well  Gas Well  D&A  Cathodic  Water Supply Well  
 SWD Docket # \_\_\_\_\_  ENHR Docket # \_\_\_\_\_  Other: \_\_\_\_\_

Conductor Casing Size: \_\_\_\_\_ Set at: \_\_\_\_\_ Cemented with: \_\_\_\_\_ Sacks

Surface Casing Size: 8-5/8" Set at: 90' Cemented with: 90sx Sacks

Production Casing Size: 5-1/2" Set at: 3118' Cemented with: 125sx Sacks

List (ALL) Perforations and Bridgeplug Sets: Open Hole

Elevation: 1236 ( G.L. /  K.B.) T.D.: 3135 PBTD: \_\_\_\_\_ Anhydrite Depth: 440"  
(Stone Corral Formation)

Condition of Well:  Good  Poor  Casing Leak  Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): Per KCC instructions

Is Well Log attached to this application as required?  Yes  No Is ACO-1 filed?  Yes  No

If not explain why? \_\_\_\_\_

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: Mike Anstine

Phone: ( 620 ) 218 - 1822

Address: P.O. Box 729 - 102 S. River Rd. City / State: Oxford, Kansas

Plugging Contractor: B.P.C. Well Plugging KCC License #: 32475  
(Company Name) (Contractor's)

Address: P.O. Box 282 Burden, Ks. 67019 Phone: ( 620 ) 438 - 2856

Proposed Date and Hour of Plugging (if known?): ASAP

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 10-30-2006 Authorized Operator / Agent: [Signature]  
(Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED  
NOV 03 2006  
KCC WICHITA

DRILLERS' LOG

SUN OIL COMPANY  
 Brown No. 4  
 NE/4-NE/4 E1/4  
 Sec. 2, Twp. 34S, Rge. 5E  
 Cowley County, Kansas

FORMATION	FROM	TO	
Shale, shells	0	100	elev. DF 1236'; Ord. 1234'
Shale, lime, shells	100	440	
Shale, shells	440	1240	Drilling Commenced 12-10-56
Shale, lime	1240	2300	Drilling Completed 12-23-56
Sdy. lay. shale	2300	2359	Date First Production 12-26-56
Sand (Leyton) water	2359	2393	
Sdy. shale	2393	2413	
Sand (water)	2413	2456	
Sdy. shale	2456	2512	
Shaly lime (Kans. City)	2512	2543	
Shaly sand	2543	2554	
Shale, lime	2554	2652	8-5/8" OD 24 1/2 SS 535 set at 96', cemented w/90 max reg., circulated.
Sdy. shale	2652	2738	
Lime (Marston)	2738	2748	5 1/2" OD 14 1/2 SS set at 3118', cemented w/125 sax. Top cement 2475'.
Limey shale	2748	2758	
Lime, str. shale	2758	2873	
Sdy. sh. (Cherokee)	2873	2937	
Limey shale	2937	2960	
Lime	2960	2968	Casing set in top of Miss. Chat, drilled in with cable tools 3121'-3135'.
Sdy. sh., str. lime	2968	3111	
Conglomerate	3111	3115	
Chat (Miss.) oil & gas	3115	3133	
Chat - white	3133	3134	
Lime	3134	3135	
		T.D.	

I hereby certify that the foregoing is a true and correct copy of the Brown No. 4 well log as recorded on the books of Sun Oil company, Tulsa, Oklahoma.

*J. W. Strickland*  
 J. W. Strickland

STATE OF OKLAHOMA )  
 ) SS  
 COUNTY OF TULSA )

Subscribed and sworn to before me this 16 day of January, 1957.

*Blanche Jones*  
 Blanche Jones  
 Notary Public

My Commission Expires:  
May 9, 1957

RECEIVED  
 NOV 03 2006  
 KCC WICHITA

# KANSAS

CORPORATION COMMISSION

Kathleen Sebelius, Governor    Brian J. Moline, Chair    Robert E. Krehbiel, Commissioner    Michael C. Moffet, Commissioner

## NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

W.D. Short Oil Co., LLC  
102 S. River Road  
PO Box 729  
Oxford, KS 67119

November 13, 2006

Re: BROWN #4  
API 15-035-02109-00-00  
NENESW 2-34S-5E, 2310 FSL 2310 FWL  
COWLEY COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.


Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

**Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

**This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.**

Sincerely



Barry Metz  
Deputy Director

District: #2  
3450 N. Rock Road, Suite 601  
Wichita, KS 67226  
(316) 630-4000