

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION

WELL PLUGGING APPLICATION

Please TYPE Form and File ONE Copy

Form CP-1
September 2003
This Form must be Typed
Form must be Signed
All blanks must be Filled

API # 15 - 167-20089-00-00 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued, indicate original spud or completion date 8/3/1967.

Well Operator: Robinowitz Oil Company KCC License #: 8663 6883
(Owner / Company Name) (Operator's)

Address: 4200 E Skelly Drive, Suite 620 City: Tulsa

State: Oklahoma Zip Code: 74135-3210 Contact Phone: (918) 481 - 7130

Lease: Davidson Well #: 9 Sec. 33 Twp. 15 S. R. 11 East West

SE - SW - SW Spot Location / QQQQ County: Russell

KCCW #
330
4290

330 Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)

4290 Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well
 SWD Docket # _____ ENHR Docket # _____ Other: _____

Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks

Surface Casing Size: 8 5/8" Set at: 485' Cemented with: 250 Sacks

Production Casing Size: 5 1/2" Set at: 3280' Cemented with: 75 Sacks

List (ALL) Perforations and Bridgeplug Sets: Arbuckle 3268' to 3274' Open Hole

Elevation: 1818' (G.L. / K.B.) T.D.: 3288' PBDT: None Anhydrite Depth: 671'
(Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): per KCC Specifications

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

If not explain why? _____

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: Don Degenhardt

Phone: (620) 587 - 3936

Address: 1885 NE 100 Avenue City / State: Clafin, KS

Plugging Contractor: Mike's Testing & Salvage KCC License #: 31529
(Company Name) (Contractor's)

Address: PO Box 467, Chase KS 67524-0209 Phone: (620) 938 - 2943

Proposed Date and Hour of Plugging (if known?): _____

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 9/21/06 Authorized Operator / Agent: _____
(Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
SEP 25 2006
KCC WICHITA

W E L L L O G

Date Commenced: August 3, 1967
 Date Completed: August 9, 1967

Robinowitz Oil Company
 DAVIDSON #9
 SE/4 SW/4 SW/4
 Section 33-T15s-R11w
 Russell County, Kansas

0	-	80'	Clay Post rock
80	-	300'	Shale & Shells
300	-	360'	Red Bed & Shale
360	-	470'	Hard Sand
470	-	671'	Red Bed
671	-	692'	Anhydrite
692	-	1200'	Red Bed Shale & Shells
1200	-	1670'	Shale & Lime
1670	-	1860'	Lime & Shale
1860	-	2607'	Shale & Lime
2607	-	2847'	Lime
2847	-	2851'	Shale
2851	-	2867'	Lime Shale
2867	-	2880'	Lime
2880	-	2942'	Shale & Sand
2942	-	2958'	Brown lime - Shale
2958	-	3220'	Lime
3220	-	3234'	Lime - Shale
3234	-	3263'	Conglomerate Shale
3263	-	3278'	Chert
3278	-	3288'	Dolomite

ELEVATION: 1818 K.B.

FORMATION DATA:

Anhydrite	671
Heebner	2847
Brown Lime	2942
Lansing	2958
Arbuckle	3278
R.T.D.	3288

SURFACE CASING: Set 8-5/8"
 at 485' w/250 sacks cement

RECEIVED
 SEP 25
 KCC WICHITA

PRODUCTION CASING: Set
 5 1/2" casing at 3280' with
 75 sacks cement & 200
 gallons latex.

A F F I D A V I T

STATE OF KANSAS
 COUNTY OF BARTON) ss.

Lynn O. Duke, of lawful age, does swear and state that
 the facts and statements herein contained are true and correct
 to the best of his knowledge.

Lynn O. Duke
 Lynn O. Duke

Subscribed and sworn to before me this 17 day of August, 1967.

My Comm. Expires:
4-11-70

Notary M. Hague
 Notary Public

KANSAS

CORPORATION COMMISSION

Kathleen Sebelius, Governor Brian J. Moline, Chair Robert E. Krehbiel, Commissioner Michael C. Moffet, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

Robinowitz Oil Company
4200 E Skelly Dr Ste 620
Tulsa, OK 74135-3210

October 19, 2006

Re: DAVIDSON #9
API 15-167-20089-00-00
SESWSW 33-15S-11W, 330 FSL 4290 FEL
RUSSELL COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.


Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

District: #4
2301 E. 13th
Hays, KS 67601
(785) 625-0550

Sincerely



Barry Metz
Deputy Director