

STATE OF KANSAS
KANSAS CORPORATION COMMISSION
CONSERVATION DIVISION
130 South Market - Room 2078
Wichita, Kansas 67202

FORM CP-1 (3/92)

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

API # 15-141-20,327-00-00 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR Eagle Creek Corporation KCC LICENSE # 30129
(owner/company name) (operator's)

ADDRESS 107 N. Market, Suite 509 CITY Wichita,

STATE Kansas ZIP CODE 67202 CONTACT PHONE # (³¹⁶) 264-8044

LEASE Hobrock WELL# 1-16 SEC. 16 T. 10S R. 15 (East/West)

100' - E - SW - NE SPOT LOCATION/QQQQ COUNTY Osborne

1980 FEET (in exact footage) FROM S/N (circle one) LINE OF SECTION (NOT Lease Line)

1880 FEET (in exact footage) FROM E/W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL GAS WELL D&A SWD/ENHR WELL DOCKET# _____

CONDUCTOR CASING SIZE 8 5/8" SET AT _____ CEMENTED WITH _____ SACKS

SURFACE CASING SIZE 8 5/8" SET AT 266.6' CEMENTED WITH 170 SACKS

PRODUCTION CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: _____

ELEVATION 1835'/1840' T.D. 3500' PBTD _____ ANHYDRITE DEPTH 1040'-1077'
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD POOR CASING LEAK _____ JUNK IN HOLE _____

PROPOSED METHOD OF PLUGGING 1st plug at 1040' with 25 sks

2nd plug at 590' with 100 sks

3rd plug at 310' with 40 sks

4th plug at 40' with 10 sks

15 sks rathole TOTAL 190 sks

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? _____ IS ACO-1 FILED? Enclosed

If not explain why? N/A

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Anthony Martin PHONE# 913 743-5443

ADDRESS Box 294, 533 N. Main City/State Wameeney, KS. 67672

PLUGGING CONTRACTOR Abercrombie RTD, Inc. KCC LICENSE # 30684

(company name) (contractor's)

ADDRESS 150 No. Main, Ste 801, Wichita, Ks. 67202 PHONE # (³¹⁶) 262-1841

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) 7:30 p.m. on 12-10-96

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 01-09-97 AUTHORIZED OPERATOR/AGENT

Anthony Martin
(signature)