

15-141-00020-00-00


WELL PLUGGING RECORD

STATE OF KANSAS STATE CORPORATION COMMISSION

Give All Information Completely Make Required Affidavit Mail or Deliver Report to: Conservation Division State Corporation Commission 800 Bittling Building Wichita, Kansas

OR FORMATION PLUGGING RECORD Strike out upper line when reporting plugging of formations.

Osborne County, Sec. 15 Twp. 10 Rge. 15 (W) Location as "NE 1/4 NW 1/4 SW 1/4" or footage from lines NW NW SE Lease Owner: Sohio Petroleum Company Lease Name: Schloh Well No. 1 Office Address: Russell, Kansas Character of Well (completed as Oil, Gas or Dry Hole): Dry Hole Date well completed: July 10 19 50 Application for plugging filed: July 11 19 50 Application for plugging approved: 19 Plugging commenced: July 10 19 50 Plugging completed: July 10 19 50 Reason for abandonment of well or producing formation: No commercial shows If a producing well is abandoned, date of last production: 19 Was permission obtained from the Conservation Division or its agents before plugging was commenced?: Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well: Producing formation: Depth to top: Bottom: Total Depth of Well: 3529 Feet Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Table with 7 columns: Formation, Content, From, To, Size, Put In, Pulled Out. Row 1: 8 5/8, 121', None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

3529' to 120' Heavy mud
120' to 35' Wood plug & 15 sacks mud
35' to Bottom of cellar--Wood plugs & 10 sacks cement

Received 7-17-50

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to: Address:

STATE OF Kansas, COUNTY OF Russell, ss. J. H. Bond (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. H. Bond (Address)

SUBSCRIBED AND SWORN TO before me this 12 day of July, 19 50

My Commission Expires July 2, 1953

My commission expires 22-2625 2-48-15M

Russell M Miller Notary Public

PLUGGING FILE SEC 15 Twp 10 R 15a BOOK PAGE 16 LINE 300

15-141-00020-00-00

CONTRACTOR'S VERIFIED LOG

Operator Sohio Petroleum Company Farm Name Schloch Well No. 1
 Location NW NW SE 15-108-15W
 Pool Name _____ County Osterne State Kansas
 Commencement Date June 28, 1950 Completion Date July 10, 1950

LOG OF WELL

Depth		Formation	Deviation from Vertical (Degrees)	Remarks
From	To			
0	40	clay and post rock		
40	45	sand		
45	121	blue shale		
121	310	blue shale and gusbo		
310	575	sand, chls and streaks red bed		
575	685	chalk, shale and sand		
685	845	sand, shal & shells		
845	1012	shale & red bed		
1012	1043	anhydrite		
1043	1419	Blue shale & shells		
1419	1570	salt, shale & shells		
1570	1710	lime & shale		
1710	1865	lime & shale		
1865	1940	lime & shale (hard)		
1940	2040	lime & shale		
2040	2059	lime (hard)		
2059	2165	lime & shale		
2165	2175	sandy		
2175	2310	lime & shale		
2310	2540	lime & shale		
2540	2635	lime & shale		
2635	2880	lime		
2880	3000	lime		
3000	3115	lime		
3115	3210	lime		
3210	3320	lime		
3320	3430	lime		
3430	3469	conglomerate		
3469	3492	conglomerate & chert		
3492	3529	lime & chert		
3529		Total Rotary Depth		

PLUGGING
 FILE SEC 15 T 10 R 1520
 BOOK PAGE 16 LINE 3

Received
 8-23-50