


15-141-00057-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Osborne County. Sec. 11 Twp. 10S Rge. 15 ~~xxxxx~~ (W)
Location as "NE/CNW/SW" or footage from lines NE NE NE
Lease Owner D. R. Lauck Oil Company, Inc.
Lease Name Meyer Well No. 1
Office Address 301 South Broadway Wichita 2 Kans
Character of Well (completed as Oil, Gas or Dry Hole) dry hole
Date well completed Hyky July 2 19 57
Application for plugging filed July 2 19 57
Application for plugging approved July 2 19 57
Plugging commenced July 2 19 57
Plugging completed July 2 19 57
Reason for abandonment of well or producing formation Dry hole
If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well _____
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3775 Feet
Show depth and thickness of all water, oil and gas formations.


OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	213'	8 5/8"	213	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Hole filled with mud 3775' to 210'
plug, rock bridge & 20
sax cement 210' to 170'
mud 170' to 40'
plug 40' to 36'
cement 36' to 6' bottom of cellar



(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sun Cementing Company
Address Great Bend Kansas

STATE OF Kansas, COUNTY OF Sedgwick ss.
John H. Knightley (employee of owner) by of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) John H. Knightley
Wichita Kans
(Address)

SUBSCRIBED AND SWORN TO before me this 7 5th day of July, 19 57

My commission expires Sept. 14, 1959

Elizabeth Gay
Notary Public.

PLUGGING
FILE SEC 11 T. 10 R. 15W
BOOK PAGE 26 LINE 5

15-141-00057-00-00

D. R. Lauck Oil Company, Inc.

NE NE NE Sec. 11-10S-15W
Osborne County Kansas

Meyer #1

Commenced: June 20, 1957
Completed: July 2, 1957

Casing Record: 213' 8 5/8" cemented w/165 sacks

Elevation: GR 1853; DF 1856; KB 1858;

Drillers Log

Shale & shells	540
sand	560
shale	690
sand	780
shale & red bed	1097
Anhydrite	1120
shale, shells & red bed	1430
shale & shells	1650
lime & shale	1900
lime	1935
lime & shale	2840
lime	3035
lime & shale	3100
lime	3425
lime & shale	3505
shale	3571
chert, lime & shale	3665
lime & shale	3722
Arbuckle	3775
Rotary Total Depth	3775

	<u>Tops</u>	
	<u>Sample</u>	<u>Halliburton</u>
Anhydrite	1097 + 761	
Heebner	3031 -1173	3028-1170
Toronto	3053-1195	3051-1193
Lansing	3081-1223	3078-1220
Base Kansas City	3350-1492	3349-1491
Conglomerate	3467-1609	3462-1604
Viola	3612-1754	2609-1751
Simpson	3696-1838	3697-1839
Arbuckle	3722-1864	3722-1864
Rotary Total Depth	3775-1917	3775-1917

DST #1 (W) 3037-3067 open 1 hour; weak blow
6 min; recov. 5' mud;
BHP 240#, 20 min.

D & A

RECEIVED
CORPORATION COMMISSION
7-10-57
JUL 10 1957
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC. 11 T. 10 R. 15W
BOOK PAGE 26 LINE 5