

15-141-00633-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittling Building  
Wichita, Kansas

Osborne County. Sec. 7 Twp 10S Rge 15 (E) (W)

Location as "NE/CNW 1/4 SW 1/4" or footage from lines NE 1/4 NE 1/4 NW 1/4

Lease Owner John Lindas Oil, Inc.

Lease Name Pfortmiller Well No. 1

Office Address 1314 Union National Bank Bldg., Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry

Date well completed 8-15-51 19

Application for plugging filed 8-15-51 19

Application for plugging approved 8-15-51 19


Plugging commenced 8-15-51 19

Plugging completed 8-15-51 19

Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production Dry 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Name of Conservation Agent who supervised plugging of this well Petty-Stough KCC Zap

Producing formation Depth to top Bottom Total Depth of Well 3622 3610 feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"	192'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with heavy mud to 190'. Set plug, 15 sacks cement through drill pipe.

Set another plug 35 feet from base of cellar, 10 sacks cement. Plugging completed

12:30 A. M. 8-16-51

RECEIVED  
STATE CORPORATION COMMISSION  
8-18-51  
AUG 18 1951

CONSERVATION DIVISION  
Wichita, Kansas

Name of Plugging Contractor John Lindas Oil, Inc.

Address 1314 Union National Bank Bldg., Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.

Scott Stuckey (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Scott Stuckey

1314 Union National Bank Bldg., Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 17th day of August, 1951.

Mabel Kelly

Notary Public.

My commission expires Feb. 11, 1954

23-8390-s 6-51-20M

PLUGGING  
FILE SEC-7 T-10 R-15W  
BOOK PAGE 104 LINE 6

15-141-00033-00-00

TCC

DRILLING LOG

To: John Lindas Oil, Inc.,  
1314 Union National Bank Building,  
Wichita 2, Kansas.

Lease: Pfortmiller #1. County: Osborne, Kansas  
Section: 7-10-15  
Location: NE $\frac{1}{4}$  NE $\frac{1}{2}$  NW $\frac{1}{2}$   
Elevation: 1945' R.B.  
Field: Wildcat

Rotary Total Depth: 3610' *15' of TCC*  
Commenced: 8-3-51. Completed: 8-16-51.  
Casing: 8-5/8" @ 192' With 115 sacks of cement and 2 sacks Calcium Chloride.  
5-1/2" @ None - D & A.

Contractor: JOHN LINDAS OIL, INC., Rig #2,  
1314 Union National Bank Building,  
Wichita 2, Kansas.

FIGURES INDICATE BOTTOM OF FORMATIONS

0	to	83	Surface Sand & Clay
83		188	Soil Clay
188		192	Shells
192		498	Shale & Shells
498		875	Gip Red Bed
875		1125	Soil Shale & Red Bed
1125		1175	Shale & Anhydrite
1175		1350	Sand Salt & Shells
1350		1720	Shale & Shells
1720		2115	Lime & Shale
2115		2190	Shale & Lime
2190		2432	Lime & Shale
2432		2510	Shale
2510		2670	Shale & Shells
2670		2795	Sandy Shale & Lime
2795		2960	Shale
2960		2995	Shale & Lime
2995		3020	Lime
3020		3077	Shale & Lime
3077		3330	Lime
3330		3400	Cherty Lime & Shale
3400		3450	Lime & Chert
3450		3520	Lime
3520		3590	Conglomerate
3590		3610 TD	Lime.

STATE OF KANSAS)  
) ss  
COUNTY OF SEDGWICK)

I, the undersigned, being duly sworn on oath, state that the above statement and log is a true and correct record and log of the well drilled at the location above described.

JOHN LINDAS OIL, INC.

By Scott Husky

Subscribed and sworn to before me, this 21st day of August, 1951.

8-22-51  
AUG 22 1951

Mabel Dally  
Notary Public

My commission expires the 11th day of February, 1954.

**PLUGGING**  
FILE SEC 2 T 10 R 15 W  
BOOK PAGE 107 LINE 6