

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-063-21584-00-00
Spot: SENESW Sec/Twnshp/Rge: 8-14S-26W
1650 feet from S Section Line, 2310 feet from W Section Line
Lease Name: HERL 8C Well #: 1
County: GOVE Total Vertical Depth: 4380 feet

Operator License No.: 6039
Op Name: L.D. DRILLING, INC.
Address: RR 1 BOX 183B 7 SW 26TH AVENUE
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	4379	0	190 SX
SURF	8.625	234	0	165 SX

\$ 142.35

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/07/2006 10:00 AM
Plug Co. License No.: 6039 Plug Co. Name: L.D. DRILLING, INC.
Proposal Rcvd. from: MIKE KASSELMAN Company: L.D. DRILLING, INC. Phone: (620) 793-3051

Proposed Plugging Method: Ordered out 350 sxs 60/40 pozmix - 10% gel - 500# hulls.
DV at 2025' w/275 sxs.

Plugging Proposal Received By: JAY PFEIFER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/07/2006 12:00 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Swaged onto 4 1/2" - mixed and pumped 300 sxs cement with 450# hulls.
Max. P.S.I. 600#. S.I.P. 350#.
Instant 500# on the annulus.

Perfs:

Top	Bot	Thru	Comments
4362	4363		
4349	4354		
4268	4271		
4255	4257		

INVOICED
DATE 11-15-06
INV. NO. 2007060810

Remarks: COPELAND ACID AND CEMENTING.

Plugged through: CSG

District: 04

Signed _____

(TECHNICIAN)

RECEIVED

NOV 13 2006

KCC WICHITA

Form CP-2/3

NOV 08 2006

PBT

RITCHIE EXPLORATION
WICHITA KS 67278-3188

WILDCAT

8-14S-26W
SE NE SW

#1 HERL 8C

site: 7-1/4 S & 13-1/4 E OF GOVE KS
contr: LD DRILLING #1
geol: KIM B. SHOEMAKER

cy: GOVE
field: WC (GOHERL DISC)

API 15-063-21584

fr date 01/20/2004
spc date 01/29/2004
drig comp 02/08/2004
card issued 06/28/2004
last revised 06/28/2004

ELV: 2539 KB, 2534 GL
tops.....depth/datum
RTD.....4380 -1841
NO TOPS RPTD

IP status
OIL, P 1 BOPD, NW, MARM 4255-4271 OA, MISS 4349-4363
OA, 02/17/2004
CSG: 8-5/8" 234 / 165 SX (ALT 2), 4-1/2" 4379 / 175 SX, MULTI
STAGE COLLAR AT 2025 / 200 SX
COMMENT: MI & RURT 1/28/2004
NO CORES
DSTS TAKEN - DETAILS NA
TRGT ZN: MISS (OIL), PTD 4400 (MISS), MICT - CO, PF
(MISS) 4349-4354, 4362.5-4363, W / 2 SPF, AC 700 GAL (20%
FE), SWB LD, SO, PF (FT SC) 4255-4257, 4268-4271, W / 2
SPF, AC 1100 GAL (20% FE), SWB LD, SO, SET 2-3/8" TBG
AT 4358, NO PKR, POP, IPP 1 BOPD, NW, DOFP 2/17/2004,
COMMINGLED - NO OTHER INFO AVAILABLE - TEMP
COMP 6/28/2004

COPYRIGHT 2004
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS