

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-20284-00-00
Spot: SESENE Sec/Twnshp/Rge: 5-22S-14W
2310 feet from N Section Line, 330 feet from E Section Line
Lease Name: ESTES Well #: 3
County: STAFFORD Total Vertical Depth: 3853 feet

Operator License No.: 5631
Op Name: LOEWEN OPERATOR, INC.
Address: 208 S. MAIN PO BOX 335
CANTON, KS 67428

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3851	0	
SURF	8.625	450		

\$ 125.22

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/01/2006 12:30 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Revd. from: DOUG LOEWEN Company: LOEWEN OPERATOR, INC Phone: (620) 727-3410

Proposed Plugging Method: SANDED TO 3800' & 5 SX CMT ON TOP OF SAND WITH A DUMP BAILER. RAN TUBING TO 900'. PUMPED 80 SX CMT CIRCULATING TO SURFACE UP 4 1/2". PRESSURED 8.625 X 5.5 ANNUALS WITH CMT TO 600 PSIG. SHUT IN PRESSURE 600 PSIG. PULLED TUBING AND TAPPED OFF HOLE WITH 40 SX CMT.

Plugging Proposal Received By: RICHARD LACEY Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/01/2006 3:15 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

SANDED TO 3800' & 5 SX CMT ON TOP OF SAND WITH A DUMP BAILER. RAN TUBING TO 900'. PUMPED 80 SX CMT CIRCULATING TO SURFACE UP 4 1/2". PRESSURED 8.625 X 5.5 ANNUALS WITH CMT TO 600 PSIG. SHUT IN PRESSURE 600 PSIG. PULLED TUBING AND TAPPED OFF HOLE WITH 40 SX CMT.

Perfs:

INVOICED
DATE 11-15-06
INV. NO. 2007060811

Remarks: USED 60/40 POZMIX 6% GEL BY QUALITY CEMENTING.

Plugged through: TBG

District: 01

Signed

Steve Herant for RWC
(TECHNICIAN)

RECEIVED Form CP-2/3

NOV 14 2006

KCC WICHITA

PET