

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-20287-00-00
Spot: NWSENE Sec/Twnshp/Rge: 5-22S-14W
1650 feet from N Section Line, 990 feet from E Section Line
Lease Name: ESTES Well #: 4
County: STAFFORD Total Vertical Depth: 3880 feet

Operator License No.: 5631
Op Name: LOEWEN OPERATOR, INC.
Address: 208 S. MAIN PO BOX 335
CANTON, KS 67428

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3880	1830	100 SX
SURF	8.625	542		300 SX

\$ 126.10

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/31/2006 1:30 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: DOUG LOEWEN Company: LOEWEN OPERATOR, INC Phone: (620) 628-4425

Proposed Plugging Method: SANADED TO 3470 AND 5 SX CMT. 1ST PLUG AT 930' WITH 15 SX GEL-50 SX CMT. 2ND PLUG AT 570' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 15 SX CMT.

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 10/31/2006 2:45 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

SANADED TO 3470 AND 5 SX CMT WITH DUMP BAILER. SPOTTED PLUGS THROUGH CASING. 1ST PLUG AT 930' WITH 15 SX GEL-50 SX CMT. 2ND PLUG AT 570' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 15 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3580	3618		

INVOICED
DATE 11-15-06
INV. NO. 200706081

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED CEMENTING. RECOVERED 1830' OF 5 1/2 CASING.

Plugged through: CSG

District: 01

Signed

Steve Durrant for RWC

(TECHNICIAN)

RECEIVED

NOV 14 2006

Form CP-2/3

KCC WICHITA

PBT