

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-047-20672-00-00  
Spot: NESWNW Sec/Twnshp/Rge: 16-26S-18W  
1650 feet from N Section Line, 990 feet from W Section Line  
Lease Name: BELCHER Well #: 1  
County: EDWARDS Total Vertical Depth: 4868 feet

Operator License No.: 9228  
Op Name: MARLIN OIL CORPORATION  
Address: PO BOX 14630  
OKLAHOMA CITY, OK 73113

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4180		
PROD	4.5	4849	2165	150 SX CMT # 158.21
SURF	8.625	372		275 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/06/2006 9:00 AM  
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.  
Proposal Rcvd. from: DICK LYNN Company: MARLIN OIL COMPANY Phone: (405) 818-8738

Proposed Plugging Method: DISPLACE 20 SX CMT PLUG W/MUD TO PLUG PERFS @ 4228-4331'. CUT OFF 4-1/2" CSG AS DEEP AS POSSIBLE. PLACE 75 SX CMT PLUG FROM 422' TO 322' AND A 10 SX CMT PLUG FROM 34-4'. WELD ON ID COVER PLATE.

Plugging Proposal Received By: RICHARD LACEY WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 10/06/2006 10:00 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SET CI BP AT 4180 & PUT 4 SX CMT ON TOP OF CIBP. SPOT PLUGS THRU 2 3/8 TBS. 1ST PLUG AT 1280' WITH 50 SX CMT. 2ND PLUG AT 422 WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4682	4704		
4329	4331		
4282	4287		
4228	4232		

**INVOICED**  
DATE 11-15-06  
INV. NO. 2007060812

Remarks: USED CLASS "A" CEMENT BY ORR ENTERPRISES. RECOVERED 2165 OF 41/2" CASING.

Plugged through: TBG

District: 01

Signed Steve Pfeifer for S.P.  
(TECHNICIAN)

RECEIVED  
Form CP-2/3  
NOV 14 2006  
KCC WICHITA PKT