

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-145-20818-00-00

Spot: S2SW

Sec/Twnshp/Rge: 4-23S-17W

660 feet from S Section Line, 3960 feet from E Section Line

*PKT Per RB DMS
per Dist #1*

Lease Name: WELCH

Well #: 4-1

County: PAWNEE

Total Vertical Depth: 4325 feet

Operator License No.: 9781

Op Name: GRANDY, DARRELL D.

Address: PO BOX 922
HOOKER, OK 73945

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	4324	2000	200 SX
SURF	8.625	371		275 SX CMT

\$140.50

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 10/24/2006 1:00 PM

Plug Co. License No.: 31529

Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.

Proposal Rcvd. from: MIKE KELSO

Company: MIKES TESTING & SALVAGE INC. Phone:

Proposed Plugging Method: SANDED BOTTOM TO 4130' & 5 SX CMT PLUG AT 1120' 15 SX CMT. PLUG AT 400' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: RICHARD LACEY

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 10/25/2006 3:00 PM

KCC Agent: RICHARD LACEY

Actual Plugging Report:

SANDED BOTTOM TO 4130' & 5 SX CMT WITH DUMP BAILER. SPOTTED PLUGS THROUGH CASING WHILE PULLING. 1ST PLUG AT 1120" WITH 15 SX GEL - 50 SX CMT. 2ND PLUG AT 400' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4183	4234		

INVOICED
DATE 11-15-06
INV. NO. 2007060806

Remarks: USED 60/40 POZMIX 6% GEL BY COPELAND ACID. RECOVERED 2000 OF 41/2" CASING.

Plugged through: CSG

District: 01

Signed

Steve Stewart for RWC

(TECHNICIAN)

RECEIVED

Form CP-2/3

NOV 14 2006

PKT

KCC WICHITA

1