

3-15

4-041661

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15-141-20,295-00-00

NW SE SE /4 SEC. 07, 10 S, 15 W  
990 feet from S section line  
990 feet from E section line

Operator license# 30129

Lease Pfortmiller well # 1-7

Operator: Eagle Creek Corporation

County Osborne 113.75

Address: 107 N. Market  
Suite #509  
Wichita, Kansas 67202

Well total depth 3500 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 264 feet

Aband. oil well     , Gas well     , Input well     , SWD     , D & A X

Plugging contractor: Pickrel Drilling, Inc. License# 5123

Address: \_\_\_\_\_

Company to plug at: Hour: P.M. Day: 15 Month: March Year: 95

Plugging proposal received from: Doyle Folker

Company: Pickrell Drilling, Inc. Phone: \_\_\_\_\_

Were: Order 195 sxs. 60/40 pozmix - 6% gel - 1/4# flocele per. sack.  
Spot plugs through drill pipe with heavy mud between all plugs.

Plugging Proposal Received by: Dennis Hamel

Plugging operations attended by agent? All[      ], Part[      ], None[ X ]

Completed: Hour: 9:30P.M., Day: 15, Month: March, Year: 95

Actual plugging report: \_\_\_\_\_

1st. plug at 1090' w/25 sxs.

2nd. plug at 750' w/100 sxs.

3rd. plug at 300' w/40 sxs.

4th. plug at 40' w/10 sxs.

15 sxs. in rathole.

Remarks: Halliburton Cementing.

Condition of casing(in hole): GOOD      BAD      Anhy. plug: YES X NO     

Bottom plug(in place): YES     , CALC     , NO      Dakota plug: YES X, NO     

Plugged through TUBING     , CASING     . Elevation:      GL     

I did INVOICED [      ] observe the plugging. Dennis Hamel

DATE MAR 30 1995

WV. NO. 42484

(agent)  
Form CP-2/3

STATE CORPORATION COMMISSION  
WICHITA, KANSAS  
3-20-95  
MAR 20 1995