

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-135-24548-00-00  
Spot: SWNENW Sec/Twnshp/Rge: 4-16S-26W  
1251 feet from N Section Line, 1818 feet from W Section Line  
Lease Name: THORNBURG B Well #: 1-4  
County: NESS Total Vertical Depth: 4606 feet

Operator License No.: 5144  
Op Name: MULL DRILLING COMPANY, INC.  
Address: PO BOX 2758 221 N MAIN STE 300  
WICHITA, KS 67201

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	219		

\$ 149.70

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/09/2006 6:45 AM  
Plug Co. License No.: 33575 Plug Co. Name: WW DRILLING, LLC  
Proposal Rcvd. from: BILL WYNN Company: WW DRILLING, LLC. Phone: \_\_\_\_\_

Proposed Plugging Method: 1ST PLUG AT 2070' WITH 50 SX CMT. 2ND PLUG AT 1410' WITH 80 SX CMT. 3RD PLUG AT 740' WITH 40 SX CMT. 4TH PLUG AT 240 WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 15 CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CMT.

Plugging Proposal Received By: STEVE DURRANT WitnessType: NONE  
Date/Time Plugging Completed: 10/09/2006 8:45 AM KCC Agent: STEVE DURRANT

Actual Plugging Report:

1ST PLUG AT 2070' WITH 50 SX CMT. 2ND PLUG AT 1410' WITH 80 SX CMT. 3RD PLUG AT 740' WITH 40 SX CMT. 4TH PLUG AT 240 WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 15 CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CMT.

Perfs:

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED

Plugged through: DP

District: 01

Signed Steve Durrant  
(TECHNICIAN)

INVOICED  
DATE 11-15-06  
INV. NO. 2007060815

RECEIVED Form CP-2/3  
NOV 13 2006  
KCC WICHITA *PAJ*