

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-03431-00-00
Spot: N2NENE Sec/Twnshp/Rge: 11-10S-20W
4950 feet from S Section Line, 660 feet from E Section Line
Lease Name: CROFFOOT A Well #: 7
County: ROOKS Total Vertical Depth: 3799 feet

Operator License No.: 32278
Op Name: TENGASCO, INC.
Address: 1327 NOOSE ROAD PO BOX 458
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3795	0	w/unknown sxs cmt
SURF	8.625	235	0	w/unknown sxs cmt

\$ 123.47
\$ 123.47

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/09/2006 4:00 PM
Plug Co. License No.: 32278 Plug Co. Name: TENGASCO, INC.
Proposal Rcvd. from: GARY WAGNER Company: TENGASCO, INC. Phone: (785) 735-4124

Proposed Plugging Method:
Ordered out 400 sxs 60/40 pozmix - 10% gel - 800# hulls - 10/09/2006
Ordered out 50 sxs 60/40 pozmix - 10% gel.- 11/02/2006
Shot tubing off at 3435'.
Operator attempted to squeeze Dakota leak - unable - casing was in bad shape.
Decided to P/A.

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 10/09/2006 7:00 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Ran tubing to 3200'. Allied pumped 110 sxs 60/40 pozmix - 10% gel with 300# hulls.
Pulled tubing to 1700'. Allied pumped 145 sxs cement with 500# hulls - circulated cement.
PTOH. Squeezed 5 1/2" casing with 145 sxs cement.
Max. P.S.I. 300#. S.I.P. 100#.
11/02/2006 - Witnessed by Pat Staab
Allied pumped 25 sxs 60/40 pozmix - 10% gel down backside.
Max. P.S.I. 500#. Blew hole in surface pipe. Backside full of cement.
Note: Top tubing fish at 3435' (11 joints in hole).

Perfs:

Top	Bot	Thru	Comments
3795	3799	OH	

INVOICED
DATE 11-9-06
INV. NO. 2007060775

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed Richard Williams
(TECHNICIAN)

10

NOV 06 2006

RECEIVED Form CP-2/3
NOV 07 2006
KCC WICHITA

RF

I C MILLER

#7 CROFFOOT 'A'

11-10-20w

N2 NE NE

Contr. VIRGINIA DRLG

ROCKS

County

E 2234RB

Comm.

Comp. 12-27-57

IP

240 BOPD

Tops	Depth	Datum
HEEB	3454	-1220
TOR	3478	-1244
LANS	3494	-1260
B/KC	3707	-1473
CONG	3754	-1520
SIMP	3772	-1538
ABB	3795	-1561
TD	3799	-1565

Casing

8" 235

5" 3795

DST 3625-75/1 HR, 16' MUD,
SL SPKS 0, BHP 465#DST 3795-99/1 HR, 1145' CL
GSY 0, BHP 880#FU 1000' CL 0/1 HR: CO TD
SWB 45 BO/2

MARCOTTE POOL HRS

+	+	+
+	+	+
+	+	+

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS