

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

KCC PRT 11/9/06
COPS FIG'S

API Well Number: 15-063-21010-00-00

Spot: NESWSW SWNESWSW Sec/Twnshp/Rge: 21-11S-31W
966 990 feet from S Section Line, 4290 feet from E Section Line

Lease Name: WIELAND

Well #: 3

County: GOVE

Total Vertical Depth: 4550 feet

Operator License No.: 5011

Op Name: VIKING RESOURCES, INC

Address: 105 S BROADWAY, STE 730
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	4549	0	175 + 450 SX
SURF	8.625	247	0	180 SX

#147.88

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 11/01/2006 1:00 PM

Plug Co. License No.: 31627

Plug Co. Name: WHITETAIL CRUDE, INC

Proposal Rcvd. from: JIM DELVIN

Company: VIKING RESOURCES, INC.

Phone: (316) 262-2502

Proposed
Plugging
Method:

Ordered 250 sxs 60/40 pozmix - 10% gel - 600# hulls.
Plug through tubing.

Plugging Proposal Received By: HERB DEINES

Witness Type: COMPLETE (100%)

Date/Time Plugging Completed: 11/01/2006 5:50 PM

KCC Agent: DARREL DIPMAN

Actual Plugging Report:

8 5/8" surface casing set at 247' w/180 sxs.
4 1/2" production casing set at 4549' w/175 sxs.
TD 4550'. Top stage cemented with 450 sxs.
Ran tubing to 2500' - pumped 100 sxs cement with 300# hulls.
Pulled tubing to 1250' - pumped 80 sxs cement with 300# hulls - cement to surface.
Connected to 4 1/2" production casing - pumped 35 sxs cement.
Max. P.S.I. 700#. S.I.P. 100#.
Connected to 8 5/8" surface casing - pumped 1/4 sack cement.
Max. P.S.I. 600#. S.I.P. 600#.

Perfs:

Top	Bot	Thru	Comments
4388	4392		

INVOICED
DATE 11-9-06
INV. NO. 2007060776

Remarks: ALLIED CEMENTING COMPANY-TICKET #25,187.

Plugged through: TBG

District: 04

ND

Signed

Darrel Dipman

(TECHNICIAN)

RECEIVED

Form CP-2/3

NOV 07 2006

KCC WICHITA

NOV 02 2006

AK

VIKING RESOURCES
217 E. WILLIAM

#3 WIELAND


21-11-31W
NE SW SW

WICHITA, KS. 67202-4005

CONTR WHITE & ELLIS DRILLING CTY GOVE

GEOL JIM MALONEY FIELD PENNY SE

ELV 2913 KB SPD 1/29/86 CARD ISSUED 3/6/86 IP P 40 BO & 5 BWPD
2908 GL DRLG COMP 2/7/86 MARM(PAW) 4388-4392



LOG	Tops	Depth/Datum
ANH	2417+ 496
B/ANH	2444+ 469
HEEB	3902- 989
TOR	3930-1017
LANS	3946-1033
STARK SH	4158-1245
BKC	4224-1311
MARM	4257-1344
PAW	4344-1431
MYR STA	4388-1475
FT SC	4412-1499
L CHER	4438-1525
JOHN ZN	4482-1569
MISS	4524-1611
LTD	4547-1634
RTD	4550-1637

API 15-063-21,010

8 5/8 " 247 / 180SX, 4 1/2 " 4549 / 625SX
DST (1) 3962-4050 (LKC) / 30-30-30-30, REC 80' DM, W / OIL SPTS, 250' WM, SIP 1235-1256#, FP 164-452#, HP 1997-1977#, BHT 114°
DST (2) 4080-4164 (LKC) / 30-30-60-60, REC 255' DM, 65' M, W / LT OIL SPTS, SIP 1357-1336#, FP 169-169 / 169-190#, HP 2053-2033#, BHT 114°
DST (3) 4162-4200 (LKC) / 30-30-60-60, 50' GIP, REC 75' OCM, SIP 1214-1276#, FP 41-41 / 72-82#, HP 2111-2080#, BHT 115°
DST (4) 4224-4270 (CONG) / 30-30-30-30, REC 20' WM, SIP 1150-995#, FP 42-42 / 42-52#, HP 2095-2074#, BHT 115°
DST (5) 4370-4410 (PAW, MYR STA) / 30-30-60-60, REC 680' GSY MCO, 20' GSY OCM, SIP 423-423#, FP 105-180 / 211-254#, HP 2178-2136#, BHT 117°
MICT -C O, PF (MYR STA) 4388-4392, W / 2 SPF, AC 1500 GAL (CRA), GSO, SET 2 3/8 " TBG AT 4400', POP, P 40 BO & 5 BWP, 2/20/86

COPYRIGHT 1985
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS