

KCC ACT 11/13/06
per OPS Ftg's

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-19086-00-00

Spot: SWNWSESW Sec/Twnshp/Rge: 16-14S-14W

879 ~~913~~ feet from S Section Line, ~~3702~~ feet from E Section Line

Lease Name: COADY

Well #: 4

County: RUSSELL

Total Vertical Depth: 3150 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: PO BOX 399
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3150	0	w/unknown sxs cmt
SURF	7	0	0	w/unknown sxs cmt

\$102.38

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 11/06/2006 10:30 AM

Plug Co. License No.: 32128

Plug Co. Name: ROME CORPORATION DBA WESTERN WELL SERVICE

Proposal Rcvd. from: JOE SMITH

Company: AMERICAN WARRIOR, INC.

Phone: (620) 272-1023

Proposed Plugging Method: Ordered 400 sxs cement and 700# hulls. Fish at 2904'. Emergency plug.

Plugging Proposal Received By: PAT STAAB

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 11/06/2006 2:00 PM

KCC Agent: ROGER MOSES

Actual Plugging Report:

Perfs:

Ran tubing to 2003' - spotted 50 sxs cement without hulls - 50 sxs with 300# hulls.
Pulled tubing to 1250' - circulated with 100 sxs cement and 350# hulls.
Pulled all tubing and squeezed 5 1/2" casing with 30 sxs cement.
Max. P.S.I. 800#. S.I.P. 500#.
Tied to 5 1/2" x 7" - squeezed 1/2 sack cement to 350#.
Total of 230 sxs 60/40 pozmix - 10% gel and 650# hulls.

INVOICED

DATE 11-14-06

INV. NO. 2007060790

Remarks: ALLIED CEMENTING COMPANY. EVANS TANK.

Plugged through: TBG

District: 04

Signed

Roger Moses
(TECHNICIAN)

RECEIVED

NOV 09 2006

Form CP-2/3

KCC WICHITA

NOV 07 2006

PS

HERBERT B SHUMAKER

#4 COADY 'B'

16-14-14W
NW SE SW

Contr. JACKSON DRLG

RUSSELL County

E 1870RB Comm.

Comp. 6-19-59 IP


16 BOPD

Tops	Depth	Datum
TARK	2455	-585
TOP	2740	-870
HEFB	2970	-1100
TOR	2990	-1120
KC	3026	-1156
Anh	887	
ID	3150	-1280

Casing
5" 3150

PERF 2994-3128: ACID 7000

HALL-GURNEY POOL



INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS