

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

KCC #113106 PCT
per Co PS Ftg's

API Well Number: 15-051-02069-00-00
Spot: ^{SW} SWSESW Sec/Twnshp/Rge: 20-11S-16W
~~192~~ ¹⁵¹² ~~330~~ feet from S Section Line, ~~3630~~ ³⁷⁶⁸ feet from E Section Line
Lease Name: POTTER Well #: 14
County: ELLIS Total Vertical Depth: 3390 feet

Operator License No.: 9067
Op Name: DAMAR RESOURCES, INC.
Address: PO BOX 70 234 W. 11TH, STE A
HAYS, KS 67601

| String | Size | Depth (ft) | Pulled (ft) | Comment |
|--------|-------|------------|-------------|-------------------|
| PROD | 5.5 | 3390 | 1342 | w/unknown sxs cmt |
| SURF | 8.625 | 982 | 0 | w/unknown sxs cmt |

\$ 110.18

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/02/2006 10:30 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: DEAN IVES Company: DAMAR RESOURCES, INC. Phone: (785) 625-0020

Proposed Plugging Method: Ordered 350 sxs cement and 400# hulls.

Plugging Proposal Received By: BRUCE BASYE Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/03/2006 2:00 PM KCC Agent: ROGER MOSES

Actual Plugging Report:
Ran tubing to 3330' - spotted 150 sxs cement with 300# hulls.
Pulled all tubing.
Shot 5 1/2" off at 1342' - pulled two joints and spotted 150 sxs cement with 300# hulls.
Pulled to 502' and circulated with 30 sxs cement.
Pulled rest of casing - cellar full of cement.
Total of 230 sxs 60/40 pozmix - 10% gel - 600# hulls.

Perfs:

INVOICED
DATE 11-14-06
INV. NO. 2007060791

Remarks: ALLIED CEMENTING COMPANY. HERTEL TANK-WATER
Plugged through: TBG

District: 04

10-

Signed Roger L. Moses
(TECHNICIAN)

RECEIVED
NOV 09 2006
Form CP-2/3


NOV 07 2006

KCC WICHITA

FRANCO-CENTRAL OIL CO / #14 POTTER 20-11-16W
 SW SE SW
 Contr. RED TIGER DRLG ELLIS County
 E 1780RB Comm. Comp. 2-27-59 IP 100 BOPD

| Tops | Depth | Datum |
|----------|-------|-------|
| ANH | 962 | 818 |
| TOP | 2705 | -925 |
| HEEB | 2943 | -1163 |
| TOR | 2969 | -1189 |
| LANS | 2992 | -1212 |
| B/KC | 3220 | -1440 |
| SIMP SND | 3302 | -1522 |
| ARB | 3308 | -1528 |
| | | |
| TD | 3390 | -1610 |

Casing
 8" 982
 5" 3390
 DST 3285-3307/1 HR, 270' G, 1000
 CL GSY 0, BHP 858#
 DST 3310-20/30", 10' M, BHP 220#
 DST 3310-28/15", 10' M, BHP 995#
 DST 3326-46/1 HR, 225' FLD, 45'
 CL 0, 60' MDY 0, 120' OILY W,
 BHP 923#
 PERF 3326-32: SWB 15 BOPH, NW
 POTTER POOL



INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS