

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-23239-00-00
Spot: SWNWSE Sec/Twnshp/Rge: 32-9S-25W
1670 feet from S Section Line, 2475 feet from E Section Line
Lease Name: KUHN Well #: 1-32
County: GRAHAM Total Vertical Depth: 4089 feet

Operator License No.: 31790
Op Name: FREMONT EXPLORATION, INC.
Address: 12412 ST. ANDREWS DRIVE
OKLAHOMA CITY, OK 73120

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	220		

\$ 132.89

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 11/06/2006 1:00 PM
Plug Co. License No.: 33575 Plug Co. Name: WW DRILLING, LLC
Proposal Rcvd. from: CHUCK RHOADES Company: WW DRILLING, LLC Phone: (785) 743-6774

Proposed Plugging Method: Order 190 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: HERB DEINES WitnessType: NONE
Date/Time Plugging Completed: 11/06/2006 4:00 PM KCC Agent: HERB DEINES

Actual Plugging Report:

Perfs:

1st. Plug at 2225' w/25 sxs.
2nd. Plug at 1375' w/100 sxs.
3rd. Plug at 275' w/40 sxs.
4th. Plug at 40' w/10 sxs.
Rathole with 15 sxs.

INVOICED

DATE 11-14-06
INV. NO. 2007060792

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed _____

(TECHNICIAN)

RECEIVED

NOV 09 2006

KCC WICHITA

Form CP-2/3

NOV 07 2006