

TO:  
 STATE CORPORATION COMMISSION  
 CONSERVATION DIVISION - PLUGGING  
 130 SOUTH MARKET, SUITE 2078  
 WICHITA, KANSAS 67202

KCCPPT 11/9/06  
 @ PS'd Fig's.

API Well Number: 15-147-00949-00-00

Spot: N2N2NE N

Sec/Twnshp/Rge: 36-4S-20W

316 ~~4950~~ feet from S Section Line, ~~1320~~ feet from E Section Line

Lease Name: SLINKER

1353 Well #: 402

County: PHILLIPS

Total Vertical Depth: 3334 feet

Operator License No.: 31763

Op Name: BLAKE PRODUCTION CO., INC.

Address: 1601 NW EXPRESSWAY, SUITE 1200  
OKLAHOMA CITY, OK 73118

String	Size	Depth (ft)	Pulled (ft)	Comment
DVT		1480		400 SX
PROD	4.5	3325	0	150 SX
SURF	8.625	318	0	250 SX

\$108.36

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 11/02/2006 9:30 AM

Plug Co. License No.: 99998

Plug Co. Name: COMPANY TOOLS

Proposal Rcvd. from: VERNON BLAKE

Company: BLAKE PRODUCTION CO., INC.

Phone: (405) 286-9800

Proposed Plugging Method:

Ordered 175 sxs 60/40 pozmix - 10% gel - 700# hulls.

Plugging Proposal Received By: HERB DEINES

Witness Type: COMPLETE (100%)

Date/Time Plugging Completed: 11/02/2006 3:30 PM

KCC Agent: PAT STAAB

Actual Plugging Report:

Allied rigged to 4 1/2" casing - pumped 165 sxs cement with 700# hulls mixed in.  
 Max. P.S.I. 500#. S.I.P. 450#.  
 Dug out backside - cut hole in 8 5/8" casing and welded on a 2" nipple.  
 Rigged to 2" nipple and pumped 5 sxs 60/40 pozmix - cement blew out of bottom of well head.  
 No shut in pressure. Backside was standing full.

Perfs:

Top	Bot	Thru	Comments
3250	3258		
3228	3237		
3191	3199		
3178	3186		
3174	3176		
3155	3162		
3136	3142		
3103	3270		L. KC
3088	3092		TORONTO

**INVOICED**

DATE 11-9-06  
 INV. NO. 2007060772

Remarks: LEASE ORIGINALLY KNOWN AS LYNCH #2. ALLIED CEMENTING COMPANY-TICKET #26050.

Plugged through: CSG

District: 04

100

Signed

*[Signature]*

(TECHNICIAN)

RECEIVED

Form CP-2/3

NOV 07 2006

KCC WICHITA

NOV 06 2006

*[Handwritten mark]*

CITIES SERVICE #2 LYNCH 36-4-20W  
 APP C N2 N2 NE

Contr. PEEL BROTHERS, INC PHILLIPS County

E 1953 Comm. Comp. 1-6-61 IP 170 BOPD

Tops	Depth	Datum
ANH	1472	+481
TOP	2871	-918
DODGE	3088	-1135
LANS	3104	-1151
B/KC	3311	-1358
TD	3334	-1381

Casing

8" 318

4" 3325

DV 1480' x 400' x 5'

DST 3134-67/1HR, 35' o, 200' OCM, BHP  
 550-500#/30"

DST 3179-93/90", 45' GIP, 12' o, 6' SL  
 OCM, BHP 245-230#/30"

OO 3315: PERF 32/3250-58: 1 G MDY W, SC  
 o/10": 36/3228-37: 32/3191-99: 32/3178-

86: 7 GW, SC o/70": 8/3174-76: 28/3155-62  
 24/3136-42: 67 G MDY W & 17 G FR o/110"

FU 225' FL/24 HRS: ACID 6000

SLINKER POOL

+	+	+
+	+	+
+	+	+

INDEPENDENT OIL & GAS SERVICE  
 WICHITA, KANSAS