

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

*KCC 11/9/06  
PKT COPSED Ptg's  
306*

API Well Number: 15-163-01728-00-00

Spot: NENWNW nwnenhwnw Sec/Twnshp/Rge: 19-9S-20W

4950 feet from S Section Line, 4290 feet from E Section Line

Lease Name: TURNER 899 Well #: 2

County: ROOKS Total Vertical Depth: 3769 feet

Operator License No.: 30606

Op Name: MURFIN DRILLING CO., INC.

Address: 250 N. WATER, STE 300  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment	
PROD	5.5	3760	0	75 SX CMT	\$122.49
SURF	8.625	120	0	95 SX CMT	

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 11/06/2006 10:30 AM

Plug Co. License No.: 30606

Plug Co. Name: MURFIN DRILLING CO., INC.

Proposal Rcvd. from: JOHN GERSTNER

Company: MURFIN DRILLING CO., INC.

Phone: (785) 421-2103

Proposed Plugging Method: Ordered 300 sxs 60/40 pozmix - 10% gel - 500# hulls.  
Perf casing 170' - 970' - 1295'.  
Squeeze casing and backside.  
Plug through tubing.

Plugging Proposal Received By: HERB DEINES

Witness Type: COMPLETE (100%)

Date/Time Plugging Completed: 11/06/2006 11:45 AM

KCC Agent: MARVIN MILLS

**Actual Plugging Report:**

Set tubing at 1286' - pumped 95 sxs 60/40 pozmix - 10% gel with 300# hulls - had good circulation of cement.  
Removed tubing - tied onto the casing and pumped 20 sxs cement - good circulation of cement out the backside.  
Shut in and squeezed casing with 105 sxs cement and 300# hulls.  
Max. P.S.I. 400#. S.I.P. 350#.

**Perfs:**

Top	Bot	Thru	Comments
3760	3769		

**INVOICED**  
DATE 11-9-06  
INV. NO. 200 7060773

Remarks: SWIFT CEMENTING-TICKET #10766.

Plugged through: TBG

District: 04

*1007*

Signed

*Marvin Mills*

(TECHNICIAN)

RECEIVED

Form CP-2/3

NOV 08 2006

KCC WICHITA

NOV 06 2006

*[Signature]*

PALMER OIL CORPORATION

#2

TURNER

19-9-20W  
NE NW NW

22

Contr. \_\_\_\_\_ Rooks County


E 2219<sup>RD</sup> Comm. \_\_\_\_\_ Comp. 6-22-5. IP 149 BOPD  
PHY POT

Tops	Depth	Datum
ANH	1728	491
HEEB	3437	-1218
BR LM	3463	-1244
LANS	3479	-1260
CONG	3738	-1519
SIMP	3746	-1527
ARB	3759	-1540
T.D.	3769	-1550

Casing

5" 3760 AC.D 500

GRA-ROOK POCL



INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS