

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-23560-00-00
Spot: NENESE Sec/Twnshp/Rge: 4-9S-18W
2160 feet from S Section Line, 330 feet from E Section Line
Lease Name: LOVE Well #: 4-2
County: ROOKS Total Vertical Depth: 3530 feet

Operator License No.: 8914
Op Name: H & C OIL OPERATING INC.
Address: PO BOX 86
PLAINVILLE, KS 67663

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	218		

\$114.73

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 11/04/2006 9:00 PM
Plug Co. License No.: 33493 Plug Co. Name: AMERICAN EAGLE DRILLING LLC
Proposal Rcvd. from: PETE WAGNER Company: AMERICAN EAGLE DRILLING LLC Phone: (785) 434-2079

Proposed Plugging Method: Ordered 190 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: ROGER MOSES Witness Type: NONE
Date/Time Plugging Completed: 11/04/2006 11:00 PM KCC Agent: ROGER MOSES

Actual Plugging Report:

1st. Plug at 1380' w/25 sxs.
2nd. Plug at 780' w/100 sxs.
3rd. Plug at 270' w/40 sxs.
4th. Plug at 40' w/10 sxs. 8 5/8" wiper plug.
Rathole with 15 sxs.
Total of 190 sxs 60/40 pozmix - 6% gel.

Perfs:

INVOICED

DATE 11-14-06
INV. NO. 2007060793

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed

Roger Moses
(TECHNICIAN)

RECEIVED

NOV 09 2006

KCC WICHITA

Form CP-2/3

NOV 07 2006

[Handwritten signature]