

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-30111-00-00
Spot: SENESE Sec/Twnshp/Rge: 32-19S-11W
1650 feet from S Section Line, 330 feet from E Section Line
Lease Name: KNOP Well #: 1
County: BARTON Total Vertical Depth: 3349 feet

Operator License No.: 32961
Op Name: S & S OIL, L.L.C.
Address: PO BOX 86
CHASE, KS 67524

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3335	0	75 SX.
SURF	8.625	270	0	225 SX. \$ 108-84

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/31/2006 9:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: S&S OIL, LLC Phone: (620) 793-0933

Proposed
Plugging
Method:

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/01/2006 1:00 PM KCC Agent: CASE MORRIS

Actual Plugging Report:

Perforated at 550' and 1375'.
Ran tubing to 2000' - pumped 100 sxs 60/40 pozmix - 10% gel cement.
Pulled to 1000' - pumped 175 sxs cement.
Pulled to 500' - pumped 150 sxs cement.
Cement did not circulate.
11/01/2006
Tagged cement at 288' - circulated inside and outside of casing with 50 sxs cement.

Perfs:

Top	Bot	Thru	Comments
3145	3150		

INVOICED
DATE 11-15-06
INV. NO. 2007060822

Remarks: COPELAND CEMENTING COMPANY.

Plugged through: CSG

District: 04

1120

Signed

Case Morris

(TECHNICIAN)

RECEIVED

NOV 13 2006

KCC WICHITA

Form CP-2/3

NOV 08 2006

ASG

8-155 Map No. _____


OPER REX & MORRIS DRILLING CO., ET AL
Eldorado, Kansas

WELL #1 KNOP

CONTR Rex & Morris

FIELD Chase-Silica (Multi-Pay)

i.P. P 6 BOPD / 2 BWPD - Arb OH, 3355-45



S-T-R 32-19S-11W
SPOT SE NE SE
CO BARTON, Ks.
ELEV 1782 KB

(KB Sp1)

DST #1 (Lan) 3050-3145, Op 2 hrs, WB/2 hrs, 60' GIP, R
90' SOCM & 240' wtry mud, ISIP 1088#/30", FP's 47-
161#, FSIP 1023#/30"

DST #2 (Arb) 3330-37 - failed

DST #3 (Arb) 3314-37 - failed

DST #4 (Arb) 3339-49, Op 2 hrs, 60' GIP, R 480' MCO,
ISIP 1106#/30", FP's 47-190#, FSIP 801#/30", RTD
3349, No Log, 5 1/2" @3335 w/75 sx.

POP - CO 3349- RTD, 10 3/4 BO/50 MCA, CO PB
3345, 150A, SD/12 hrs, 8 1/2 BO, 500A, 1d, 4-1/3 BO /
1/2 BW/3 hrs, 1500A, 1d, 48 BO / 8 BW/8 hrs, OP, Co

P 6 BOPD / 2 BWPD - Arb OH - 3335-45 - COMPLETED on
8-11-65

Top 2661 - 879
Hb 2921 - 1139
Tor 2934 - 1152
Dg 2956 - 1174
BL 3046 - 1264
Lan 3070 - 1288
Cg 3319 - 1537
Arb 3329 - 1547
RTD) 3349 - 1567

MISCEL DATA

GEO: Paul Koontz

ELEV 1780 DF

SPUD DATE 6-18-65

FTG _____

1777 GR

DRLG COMP _____

SUPPT _____

FR by DATA 6-14-65

CSG 8" @270' w/225 Sx. 5" @3335' w/75 Sx.

COMP by 8-19-65