

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-145-20284-00-00
Spot: SWNESW Sec/Twnshp/Rge: 17-20S-20W
1650 feet from S Section Line, 1650 feet from W Section Line
Lease Name: DIXON Well #: 2
County: PAWNEE Total Vertical Depth: 4360 feet

Operator License No.: 32081
Op Name: SMOKEY VALLEY RESOURCES, INC.
Address: PO BOX 209
DEXTER, KS 67038

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	4355	1732	150 SX
SURF	8.625	301		185 SX

\$ 141.70

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/02/2006 9:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: GEORGE SALING Company: _____ Phone: (620) 894-0212

Proposed Plugging Method: SANDED TO 4300' & 5 SX CMT. PLUG AT 1450' 5 SX GEL - 50 SX CMT. PLUG 550' WITH 50 SX CMT. PLUG 330' 50 SX CMT. PLUG 40' 20 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 10/02/2006 2:00 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

SANDED TO 4300' & 5 SX CMT WITH DUMP BAILER. SPOTTED PLUGS THROUGH CASING WHILE PULLING. 1ST PLUG AT 1450' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 550' WITH 50 SX CMT. 3RD PLUG AT 330' WITH 50 SX CMT. 4TH PLUG AT 40' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4355	4360		

INVOICED
DATE 11-15-06
INV. NO. 2007060823

Remarks: USED 60/40 POZMIX 6% BY COPELAND ACID. RECOVERED 1732 OF 51/2" CASING.

Plugged through: CSG

District: 01

Signed Steve Yarrant for RUC
(TECHNICIAN)

RECEIVED Form CP-2/3
NOV 14 2006
KCC WICHITA

PREP