

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-145-20346-00-00  
Spot: NWNWSW Sec/Twnshp/Rge: 17-20S-20W  
2310 feet from S Section Line, 330 feet from W Section Line  
Lease Name: DIXON Well #: 3  
County: PAWNEE Total Vertical Depth: 4365 feet

Operator License No.: 32081  
Op Name: SMOKEY VALLEY RESOURCES, INC.  
Address: PO BOX 209  
DEXTER, KS 67038

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	4355	602	150 SX CMT
SURF	8.625	319		185 SX CMT

*\$141.86*

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/03/2006 1:40 PM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: GEORGE SALING Company: GEORGE SAILING Phone: (620) 894-0212

Proposed Plugging Method: SANDED BOTTOM TO 4300' & 5 SX CMT. PLUG AT 570' WITH 11 SX GEL - 50 SX CMT. PLUG AT 350' WITH 50 SX CMT. PLUG AT 40 WITH 70 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 10/03/2006 4:20 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

SANDED BOTTOM TO 4300' & 5 SX CMT WITH DUMP BAILER. PUMPED PLUGS THROUGH CASING WHILE PULLING. 1ST PLUG AT 570' WITH 11 SX GEL - 50 SX CMT. 2ND PLUG AT 350' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 70 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4355	4365		

**INVOICED**  
DATE 11-15-06  
INV. NO. 2007060823

Remarks: USED 60/40 6% GEL BY COPELAND. RECOVERED 602' OF 51/2" CASING

Plugged through: CSG

District: 01

Signed Steve Pfeifer for KCC  
(TECHNICIAN)

RECEIVED Form CP-2/3  
NOV 14 2006  
KCC WICHITA

*RFJ*