

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-05299-00-00
Spot: NENESW Sec/Twnshp/Rge: 34-11S-17W
2310 feet from S Section Line, 2970 feet from E Section Line
Lease Name: HAUSER A Well #: 5
County: ELLIS Total Vertical Depth: 3648 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 8100 E. 22ND N. BLDG. 300
WICHITA, KS 67226

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3602	0	150 SX
SURF	8.625	277	0	150 SX

\$1 118.56

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/06/2006 10:00 AM
Plug Co. License No.: 32452 Plug Co. Name: SMOKY HILLS WELL SERVICE
Proposal Rcvd. from: JOEL STULL Company: VESS OIL CORPORATION Phone: (785) 483-9169

Proposed Plugging Method: Ordered out 400 sxs 60/40 pozmix - 10% gel - 600# hulls.

Plugging Proposal Received By: JAY PFEIFER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/06/2006 2:00 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Perforated casing at 1925' - 1375' - 800'.
TIH with tubing to 3500' - mixed and pumped 140 sxs cement with 600# hulls.
Pulled up to 1500' - circulated cement with 170 sxs.
POOH. Topped with 80 sxs cement.
Instant 1500# on the annulus.

Perfs:

Top	Bot	Thru	Comments
3602	3648		OH
3334	3490		

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed Jay Pfeifer

(TECHNICIAN)

RECEIVED

NOV 13 2006

KCC WICHITA

Form CP-2/3

NOV 08 2006

INVOICED
DATE 11-15-06
INV. NO. 2007060824

PPF

CITIES SERVICE OIL COMPANY #5

HAUSER

34-11-17W
NE NE SW

Contr. _____ ELLIS _____ County

E. 2108 Comm. _____ Comp. 12-28-51 IP 163 BOPD & 4 1/2 BW

Tops	Depth	Datum
LANS	3335	-1227
B/KC	3563	-1455
SIMP SH	3581	-1473
ARB	3602	-1494
T.D.	3610	-1502

8" 277
5" 3603

DP 3610:
ACID 1000:
FMP 46 BO & 1 BW/
9 HRS

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

