

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-05904-00-00
Spot: NWNWSE Sec/Twnshp/Rge: 26-11S-17W
2310 feet from S Section Line, 2310 feet from E Section Line
Lease Name: MCCORD Well #: 6
County: ELLIS Total Vertical Depth: 3583 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 8100 E. 22ND N. BLDG. 300
WICHITA, KS 67226

| String | Size | Depth (ft) | Pulled (ft) | Comment |
|--------|-------|------------|-------------|---------|
| PROD | 5.5 | 3544 | 0 | 100 SX |
| SURF | 8.625 | 1142 | 0 | 350 SX |

PRT
~~\$ 107.00~~
\$ 116.45

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/08/2006 10:00 AM
Plug Co. License No.: 32452 Plug Co. Name: SMOKY HILLS WELL SERVICE
Proposal Rcvd. from: JOEL STULL Company: VESS OIL CORPORATION Phone: (785) 483-9169

Proposed Plugging Method: Ordered out 400 sxs 60/40 pozmix - 10% gel - 600# hulls.
Well squeezed at 1190'-1709' and 1500'-1529' w/325 sxs; 2525'-2554' w/700 sxs; 2987'-2906' w/150 sxs.

Plugging Proposal Received By: JAY PFEIFER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/08/2006 2:00 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Perforated casing at 800'.
TIH with tubing to 3500' - mixed and pumped 140 sxs cement with 600# hulls.
Pulled up to 1500' and circulated cement with 110 sxs.
POOH. Swaged onto 5 1/2" and topped with 35 sxs cement.
S.I.P. 600#. Instant 500# on the annulus.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 3544 | 3564 | | OH |

INVOICED
DATE 11-15-06
INV. NO. 2007060824

INVOICED
DATE 11-15-06
INV. NO. 2007060825

PRT

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

HO

Signed

Jay Pfeifer

(TECHNICIAN)

NOV 09 2006

RECEIVED
NOV 14 2006
KCC WICHITA

Form CP-2/3

PRT

CITIES SERVICE OIL CO #6 McCORD


26-11-17W
NW NW SE

Contr. _____ ELLIS County

E 2089 Comm. 10-30-40 Comp. 12-9-40 IP 2538 BOPD

| Tops | Depth | Datum | Casing |
|------|-------|-------|---------|
| | | | 12" 80 |
| | | | 8" 1116 |
| | | | 5" 3548 |
| | | | |
| | | | |
| | | | |
| | | | A/2500 |
| ARB | 3548 | | |
| | | | |
| | | | |
| TD | 3583 | | |

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS



8 5/8 To 1142