

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-025-21378-00-00
Spot: NWSWNW Sec/Twnshp/Rge: 6-31S-21W
1740 feet from N Section Line, 330 feet from W Section Line
Lease Name: SHRAUNER Well #: 1-6
County: CLARK Total Vertical Depth: 6510 feet

Operator License No.: 5316
Op Name: FALCON EXPLORATION, INC.
Address: 125 N. MARKET, STE. 1252
WICHITA, KS 67202

String Size Depth (ft) Pulled (ft) Comment
SURF 8.625 663

\$ 211.58

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 10/01/2006 4:00 PM
Plug Co. License No.: 5822 Plug Co. Name: VAL ENERGY, INC.
Proposal Rcvd. from: RON MOON Company: VAL ENERGY, INC. Phone: (620) 617-8147

Proposed Plugging Method: 1ST PLUG AT 6406' WITH 50 SX CMT. 2ND PLUG AT 1150' WITH 50 SX CMT. 3RD PLUG AT 700' WITH 50 SX CMT. 4TH PLUG AT 270' WITH 40 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CMT.

Plugging Proposal Received By: JIM HOLLAND WitnessType: NONE
Date/Time Plugging Completed: 10/01/2006 6:00 PM KCC Agent: JIM HOLLAND

Actual Plugging Report:

1ST PLUG AT 6406' WITH 50 SX CMT. 2ND PLUG AT 1150' WITH 50 SX CMT. 3RD PLUG AT 700' WITH 50 SX CMT. 4TH PLUG AT 270' WITH 40 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CMT.

Perfs:

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED

Plugged through: DP

INVOICED
DATE 11-15-06
INV. NO. 2007060801

District: 01

Signed Jim Holland (TECHNICIAN)

RECEIVED
NOV 13 2006
KCC WICHITA

Form CP-2/3

Handwritten initials