



JOHN CARLIN  
R. C. LOUX  
JANE T. ROY  
PHILLIP R. DICK  
CAROL J. LARSON

Governor  
Chairman  
Commissioner  
Commissioner  
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building  
WICHITA, KANSAS 67202

RECEIVED  
STATE CORPORATION COMMISSION  
6-22-82  
JUN 22 1982

15-141-20139-00-00

VERBAL PERMIT FORM  
(To be filed by Plugging Agent)

CONSERVATION DIVISION  
Wichita, Kansas

Dear Sir:

Mr. Bill Craig of Abercrombie Drilling, Inc. has this date requested permission to plug the following described well:

Operator's Full Name: Midco Exploration

Complete Address: 411 Farmers and Bankers Bldg, Wichita, Kansas 67202

Lease Name: Whisman Well No. 1

Location: SE NW NE Sec. 4 Twp. 10 Rge. 15 (E) (W)

County: Osborne Total Depth: 3670

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereafter indicated: \_\_\_\_\_

Mr. Craig was instructed to plug the well as follows:

Abhydrite 1215'-1253' Elev. 1982 KB Circulate hole and fill with mud. Pump 50 sacks cement through drill pipe at 900'. Pump 40 sacks cement through drill pipe at 240'. Fill hole with mud to 40'. Push plug and 1/2 sack hulls to 40' and cap hole with 10 sacks cement. Cement rat hole with 10 sacks cement.

Very truly yours,

Conservation Division Agent