

State of Kansas



JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202

APR 7 1982
STATE CORPORATION COMMISSION

APR 14 1982
4-14-82
CONSERVATION DIVISION
Wichita, Kansas

VERBAL PERMIT FORM
(To be filed by Plugging Agent)

Dear Sir:

Mr. Larry Hinderliter of Rains + Williamson Oil Co, Inc has this date requested permission to plug the following described well:

Operator's Full Name: Rains + Williamson Oil Co, Inc

Complete Address: 435 Page Court, 220 W. Douglas, Wichita, Kansas 67202

Lease Name: Smith Well No. 1

Location: SW NE SE Sec. 19 Twp. 10 Rge. 14 (E) (W)

County: Osborne Total Depth: 3560'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated: _____

Mr. Hinderliter was instructed to plug the well as follows:

Anh. Top 1010 Elev. 1815 KB. Circulate hole and Fill with mud.
Pump 50 sacks cement through drill pipe at 930' Pump 30 sacks
cement through drill pipe at 240'. Fill hole with mud to 40'
Push plug and 1/2 sack hulls to 40' and cap hole with 10 sacks
cement. Cement rat hole with 10 sacks cement.

Very truly yours,

[Signature]
Conservation Division Agent