

State of Kansas



JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202

June 15, 1982

VERBAL PERMIT FORM (To be filed by Plugging Agent)

Dear Sir:

Mr. John Weis of Lawbanc Drilling, Inc. has this date requested permission to plug the following described well:

Operator's Full Name: Lawbanc Drilling, Inc.

Complete Address: P.O. Box 289, Natoma, Kansas 67651

Lease Name: Beisner Well No. 1

Location: SW SW NE Sec. 6 Twp. 10 Rge. 14 (E) (W)

County: Osborne Total Depth: 3775

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated: _____

Mr. Weis was instructed to plug the well as follows:

Elev. 1954 GL. Anhydrite 1188-1219 Circulate hole and
Fill with mud Pump 50 sacks cement through drill pipe
at 900'. Pump 40 sacks cement through drill pipe at
200'. Push plug and 1/2 sack hulls to 40' and cap hole
with 10 sacks cement. Cement rat hole with 10 sacks
Cement. 50/50 Pozmix w/2% gel and 3% c.c.

Very truly yours,

Conservation Division Agent

RECEIVED
STATE CORPORATION COMMISSION
JUN 21 1982
6-21-82
CONSERVATION DIVISION
Wichita Kansas