

State of Kansas



FORM CP-2

JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202

September 14, 1981

VERBAL PERMIT FORM (To be filed by Plugging Agent)

Dear Sir:

Mr. John Weis of Lawbancro Drilling, Inc. has this date requested permission to plug the following described well:

Operator's Full Name: H. B. Chesney

Complete Address: Box 254, Natoma, Kansas 67651

Lease Name: Eileen Well No. 1

Location: NE SW NW Sec. 10 Twp. 10 Rge. 15 (W)

County: Osborne Total Depth: 3600'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated: _____

Mr. Weis was instructed to plug the well as follows:

8 7/8" - 258' - 165 sacks Anh. 1191' - 1228' Elev. 1979 KB
Circulate hole and fill with mud. Pump 50 sacks cement through
drill pipe at 980' Pump 30 sacks cement through drill pipe
at 310'. Fill hole with mud to 40'. Push plug and 1/2 sack
balls to 40' and cap hole with 10 sacks cement. Cement
rathole with 10 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION

SEP 16 1981
9-16-81
CONSERVATION DIVISION
Wichita, Kansas

Very truly yours,

Phillip R. Dick
Conservation Division Agent