

15-141-20123-00-00

FORM CP-2

State of Kansas



JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
245 North Water
WICHITA, KANSAS 67202

December 15, 1981

RECEIVED
STATE CORPORATION COMMISSION

DEC 28 1981
12-22-81
CONSERVATION DIVISION
Wichita, Kansas

VERBAL PERMIT FORM
(To be filed by Plugging Agent)

Dear Sir:

Mr. Lloyd Dellef of MurFin Drilling Co. has this date requested permission to plug the following described well:

Operator's Full Name: Northern Lights Oil Company

Complete Address: 212 N. Market, Suite 400, Wichita, Kansas 67202

Lease Name: Thompson Well No. 1

Location: C SW SW NW Sec. 7 Twp. 10 Rge. 15 (E) (W)

County: Osborne Total Depth: 3451'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated: _____

Mr. Dellef was instructed to plug the well as follows:

8 5/8" - 259 - 175 sacks Sunsect. Anti. 1106-42 Elev. ? Circulate hole and
Fill with mud. Pump 50 sacks cement through drill pipe
at 900'. Pump 50 sacks cement through drill pipe at 300'
Fill hole with mud to 40'. Push plug and 1/2 sack bulls
to 40' and cap hole with 10 sacks cement. Cement rat hole
with 10 sacks cement.

Very truly yours,

[Signature]
Conservation Division Agent