

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT REPORT

RECEIVED
STATE CORPORATION COMMISSION
FORM CP-3
JUN 22 1982
REV. 1-8-82

CONSERVATION DIVISION
Wichita, Kansas

API Number 15-141-20,139 100-00

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Midco Exploration

Complete Address 411 Farmers and Bankers Bldg., Wichita, Kansas 67202

Lease Name Whisman Well No. 1

Location SE NW NE Sec. 14 Twp. 10 Rge. 15 (~~East~~) (West)

County Oshorne Total Depth 3670

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Abercrombie Drilling, Inc. and Allied Cementing Co., Inc.

Address 801 Union Center, Wichita, Kansas License No. _____

Operation Completed: Hour: 7:55 AM Day: 16 Month: June Year: 1982

Plugging Operations attended by Agent?: All Part None

The above well was plugged as follows: Anhydrite 1215'-53' Elev. 1982 KB
Hole circulated and filled with mud. 50 sacks cement pumped through drill pipe at 900'. 40 sacks cement pumped through drill pipe at 240'. Hole filled with mud to 40'. Plug and 1/2 sack hulls pushed to 46' and hole cemented to base of cellar with 10 sacks cement. Rathole cemented with 10 sacks cement.

Cement used: 50/50 boz mix w/2% gel and 3% c.c.

Amount of Surface Casing: 8 5/8" - 250' - 180 sacks 2% gel 3% c.c.

I hereby certify that the above plugging instructions were given as herein stated.

Signed: _____
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

On vacation - called at 12:45 AM no use waking someone else!

Signed: [Signature]
Conservation Division Agent

INVOICED
DATE 6-28-82
INV. NO. 513-W