

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

API Number 15 - 141-20, 051-00-00 (of

9-22-78  
CONSERVATION DIVISION  
WICHITA, KANSAS

Operator's Full Name Par Oil Co.

Complete Address RR # 2 Box 108, Russell, Kansas 67665

Lease Name Haberer Well No. 1

Location SW NW SE Sec. 19 Twp. 10 Rge. 13 (EX) (W) X

County Osborne Total Depth 2717'

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A X

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor B & N Drlg. Co. & Sun Cementing Co.

Address Box 846 Independence, Kansas 67301 License No. \_\_\_\_\_

Operation Completed: Hour 3:30 PM Day 19 Month 9 Year 1978

The above well was plugged as follows:

Filled hole with mud and spotted 50 sx cement at 500'.

Filled hole with mud and spotted 25 sx cement at 180'.

Filled hole with mud to 40' and 1/2 sx hulls, plug, and  
10 sx cement to bottom of celler.

2 sx cement in rat hole.

196' of 8 5/8" surface casing cement circ.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Duane L Rankin  
Well Plugging Supervisor

DATE 9-26-78  
INV. NO. 8159-W